

The weights of the anchors as required by the Rules and as supplied are as set forth below:-

	<u>Rule</u>			<u>As supplied</u>		
	cwts.	qrs.	lbs.	cwts.	qr.	lbs.
1 Bower Anchor stockless	68 -	0	- 0	68 -	3	- 0
1 " " "	68 -	0	- 0	67 -	3	- 7
1 " " "	58 -	2	- 0	60 -	1	- 7
Total weight of bower anchors	<u>194 -</u>	<u>2</u>	<u>- 0</u>	<u>196 -</u>	<u>3</u>	<u>- 14</u>
1 stream anchor ex stock	19 -	0	- 0	18 -	3	- 14
stock	<u>4 -</u>	<u>3</u>	<u>- 0</u>	<u>4 -</u>	<u>3</u>	<u>- 14</u>
Wight of stream anchor including stock	<u>23 -</u>	<u>3</u>	<u>- 0</u>	<u>23 -</u>	<u>3</u>	<u>- 0</u>
1 kedge anchor ex stock	8 -	0	- 0	7 -	3	- 4
stock	<u>2 -</u>	<u>0</u>	<u>- 0</u>	<u>2 -</u>	<u>0</u>	<u>- 0</u>
	<u>10 -</u>	<u>0</u>	<u>- 0</u>	<u>9 -</u>	<u>3</u>	<u>- 4</u>

It will be observed that the weight of the stream anchor (ex stock) is 14 lbs. below the Rule Requirements, but that the weight of its stock is 14 lbs. in excess, so that the total weight of the stream anchor is in accordance with the Rules. The weight of the kedge anchor is 24 lbs. below, but the weight of the bower anchors is 1 qr. 14 lbs. above the Rule Requirements.

In view of the above the equipment of anchors is submitted for the favourable consideration of the Committee for the Figure "1".

TUE JUL 27 1920

Approved

Sie sind abwesend.

© 2021

26.7.20.

W1175-0157