

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) **K.V.J.L.**

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
149,601.		Shropshire		47/1926 Liverpool.	
No., Date, and Port of Previous Registry (if any) New Vessel					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Motor Vessel Twin Screw	Govan, Glasgow	1926	Fairfield S & E Co. Ltd. Govan, Glasgow.	
Number of Decks Three	Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths.
Number of Masts Four	aft side of the head of the stern post 		483	6.0
Rigged Fore & Aft	Length at quarter of depth from top of weather deck at			
Stern Cruiser	side amidships to bottom of keel 		499	1.0
Build Clinker	Main breadth to outside of plank 		60	3.0
Galleries None	Depth in hold from tonnage deck to ceiling at midships ...		22	8.5
Head None	Depth in hold from upper deck to ceiling at midships, in the			
Framework and description of vessel	Steel Passenger & Cargo	case of three decks and upwards 		31	8.5
Number of Bulkheads Right	Depth from top of beam amidships to top of keel 		37	0.0
Number of water ballast tanks, and their capacity in tons	Twenty-two 2393 tons	Depth from top of deck at side amidships to bottom of keel		36	6.0
		Round of beam 			7.5
		Length of engine room, if any 		80	0.0

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel **16838** Tons. Ditto per inch immersion at same depth **58.8** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
Two	Vertical direct Acting Internal Combustion	Engines.	Engines.	Engines.	Diesel	39"		2200
		and	and	Fairfield S & E Co. Ltd Govan Glasgow	Two Stroke Single Acting			9600
					28 cylinders			7700
No. of Shafts.	Particulars of Boilers.						15 knots	
Two	Description..... One	Boilers.	Boilers	Boilers.	110 Revolutions per minute			
	Number..... Steel	British	1926	Cochran & Co. Annan Ltd. Annan.				
	Iron or Steel.....							
	Loaded Pressure..... 120 lbs per sq. in.							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		5492.74	On account of space required for propelling power		3379.07
Space or spaces between Decks		2241.83	On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		444.29
Turret or Trunk		164.99	These spaces are the following, viz.:-		
Forecastle		1177.21	Forecastle, Bridge Poop and Round Houses		
Bridge space		194.30	No of Seamen or Apprentices for whom Accommodation is certified - 208		
Poop or Break		1251.31	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-		
Side Houses					
Deck Houses					
Chart House					
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		37.20			107.51
Excess of Hatchways					
Gross Tonnage		10559.58	Cubic Metres		
Deductions, as per Contra		3930.87	Master's Accommodation 13.47		
Register Tonnage		6628.71	Boatswain's Store Space 46.75		
			Steering Gear Space 36.45		
			Chart Space 6.08		
			Wireless Room Space 4.76		
			Total		3930.87

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **1345.20** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **177.16** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.


Open Space aft end of Verandah on Boat Deck L.3'.5 - 10.74 tons.

Open Space on Navigating Bridge abaft No.10 Round House L.9'3 - 8.48 tons.

Open Space on Boat Deck F.E. L.9.8 - 55.05 Tons.

Name of Master		Certificate of { Service No. Competency No.	
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
Bibby Steamship Company Limited, 26 Chapel Street Liverpool.		Arthur Harold Bibby same address. Manager	
		Sixty-four Shares.	

Dated 27th September 1926.



Lloyd's Register
Foundation

W1175 - 0178