

Rot-rept. No. 24880

Copy.

# Lloyd's Register of Shipping.



K.

Port of Düsseldorf

30th June 1936.

Order: F.0843/Flasch.188875.

E.No.35960. S.No.201.

**This is to Certify** that

Josef Loogen

the undersigned Surveyor to this Society did at the request of Messrs.Mannesmannröhren-Werke, Abt.Walzwerk of Düsseldorf-Rath test and inspect on the 6th, 11th May and 27th June 1936 at their work the undermentioned seamless Siemens-Martin Steel air receivers manufactured in accordance with the approved plan No.17938- date of approval 29.4.36. - ordered by Messrs.Motoren-Werke Mannheim A.G., vorm.Benz, Abt.Stat.Motorenbau of Mannheim.

Specification.

No.of rec.	Outs.diam.	Thickn.of shell	Length of rec.
2	450mm	9,5mm	3080mm

Results of tests.

Sample No.	Tensile str.in kg.p.sq.mm	Elongation in 200mm
27	57,0 Bend tests good.	18,5%

Hydraulic test: 853,4 lbs.p.sq.inch.  
Working pressure not to exceed: 426,7 lbs.p.sq.inch.  
For identification the receivers have been stamped as follows:

Nos.1128-1129  
LLOYDS - TEST  
853,4 lbs.  
W.P.426,7 lbs.  
J.L.27.6.36.

Fees: RM 20,--  
Expenses: RM 1,--  
Total: RM 21,--

*J. Loogen*  
Surveyor to Lloyd's Register

Düsseldorf account No.9220 v.8.7.36.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

“While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society.”