

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

Received at London Office 30 AUG 1929

Date of writing Report 19 When handed in at Local Office 28 AUG 1929 Port of Sunderland

No. in Survey held at Sunderland Date, First Survey June 6th Last Survey August 19th 1929
Reg. Book. *Supp.* (Number of Visits 7)

39227 on the S. S. Anglo-Saxon. Tons Gross 5596.21 Net 3400.66

Built at Sunderland. By whom built Short Bros Ltd. Yard No. 437 When built 1929

Owners Nitrate Producers S. S. Co Ltd. Port belonging to London.

Electric Light Installation fitted by the Sunderland Forge & Eng^g Co Ltd. Contract No. 437 When fitted 1929

System of Distribution *Double wire system*

Pressure of supply for Lighting 110 volts, Heating — volts, Power — volts.

Direct or Alternating Current, Lighting *Direct* Power —

If alternating current system, state frequency of periods per second —

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off *Yes*

Generators, do they comply with the requirements regarding rating *Yes*, are they compound wound *Yes*

are they over compounded 5 per cent. *Yes*, if not compound wound state distance between each generator —

Where more than one generator is fitted are they arranged to run in parallel —, is an adjustable regulating resistance fitted in series with each shunt field *Yes (ONE MACHINE ONLY)*

Are all terminals accessible, clearly marked, and furnished with sockets *Yes*, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched *Yes* Are the lubricating arrangements of the generators as per Rule *Yes*

Position of Generators *Engine room starboard side*

is the ventilation in way of the generators satisfactory *Yes*, are they clear of all inflammable material *Yes*

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators — and —, are the generators protected from mechanical injury and damage from water, steam or oil *Yes*

are their axes of rotation fore and aft *Yes*

Earthing, are the bedplates and frames of the generating plant efficiently earthed *Yes* are the prime movers and their respective generators in metallic contact *Yes*

Main Switch Boards, where placed *Engine room starboard side*

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard —

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes *Yes*

are they protected from mechanical injury and damage from water, steam or oil *Yes*, if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards — and —

are they constructed wholly of durable, non-ignitable non-absorbent materials *Yes*, is all insulation of high dielectric strength and of permanently high insulation resistance *Yes*

if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework *Yes*

and is the frame effectively earthed *Yes* Are the fittings as per Rule regarding: — spacing or shielding of live parts *Yes*, accessibility of all parts *Yes*, absence of fuses on back of board *Yes*, proportion of omnibus bars *Yes*, individual fuses to voltmeter, pilot or earth lamp *Yes*, connections of switches *Yes*


Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches *Double pole switch fuses on dynamo mains. Single pole switch + double pole fuses on each outgoing circuit.*

Instruments on main switchboard *one* ammeters *one* voltmeters — synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system *Earth lamps coupled earth through switches fuses.*

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules *Yes*

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule *Yes*



Cables: Single, twin, concentric, or multicore SINGLE & TWIN are the cables insulated and protected as per Tables IV or V of the Rules YES

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 5 VOLTS.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets YES

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound -

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage YES

Support and Protection of Cables, state how the cables are supported and protected LCA & B CABLES IN TWEEN DECKS, ENGINE & BOILER ROOMS WITH GALVANISED IRON CLIPS, LC 28 CABLES IN ACCOMMODATION WITH BRASS CLIPS.

If cables are run in wood casings, are the casings and caps secured by screws -, are the cap screws of brass -, are the cables run in separate grooves -. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VII YES

Refrigerator Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements YES

Joints in Cables, state if any, and how made, insulated, and protected NONE MADE.

Watertight Glands and Deck Tubes, are all cables passing through decks, and watertight bulkheads provided with deck tubes or watertight glands YES

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed YES state the material of which the bushes are made LEAD

Earthing Connections, state what earthing connections are fitted and their respective sectional areas

-, are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule YES

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven -

Navigation Lamps, are these separately wired YES, controlled by separate switch and separate fuses YES, are the fuses double pole YES

are the switches and fuses grouped in a position accessible only to the officers on watch YES

has each navigation lamp an automatic indicator as per Rule YES

Secondary Batteries, are they constructed and fitted as per Rule -

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight YES

are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected -

are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected -

-, how are the cables led

where are the controlling switches situated -

Searchlight Lamps, No. of -, whether fixed or portable -, are their fittings as per Rule -

Arc Lamps, other than searchlight lamps, No. of -, are their live parts insulated from the frame or case -, are their fittings as per Rule -

Motors, are their working parts readily accessible -, are the coils self-contained and readily removable for replacement -

are the brushes, brush holders, terminals and lubricating arrangements as per Rule -, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material -

are they protected from mechanical injury and damage from water, steam or oil - are their axes of rotation fore and aft -

if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type -

-, if not of this type, state distance of the combustible material horizontally or vertically above the motors - and -

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule -

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule -

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings -

If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office -

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	1	10	110	91	500	STEAM ENGINE.		
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

LIGHTING AND HEATING CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Conductors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	MAIN GENERATOR	2	.075	19	.072	91	30	RUBBER	LCA & B.
	EQUALISER CONNECTIONS								
	AUXILIARY GENERATOR								
	EMERGENCY GENERATOR								
	ROTARY TRANSFORMER								
	AUXILIARY SWITCHBOARDS								
	ENGINE ROOM								
	BOILER ROOM	2	.007	7	.036	16.3	30	"	"
	ACCOMMODATION (ENGINE AND								
	APT & DEPT CARGO.)	2	.007	7	.036	19.4	300	"	"
	NAVIGATION MAIN	2	.007	7	.036	3.4	360	"	"
	FOR ACCOMMOD AND CARGO.	2	.010	7	.044	14.2	304	"	"
	WIRELESS	2	.0225	7	.064	12.5	340	RUBBER	LCA & B.
	SEARCHLIGHT								
	MASTHEAD LIGHT	2	.0020	3	.029	0.36	260	"	"
	SIDE LIGHTS	2	.0020	3	.029	0.36	80	"	LCA & B.
	COMPASS LIGHTS	2	.0020	3	.029	0.18	40	"	"
	POOP LIGHTS								
	CARGO LIGHTS								
	ARC LAMPS								
	HEATERS								

MOTOR CONDUCTORS.

Ref. No.	DESCRIPTION.	No. of Motors.	Effective Area of each Conductor. Sq. Ins.	COMPOSITION OF STRAND.		Total Maximum Current. Ampères.	Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
				No.	Diameter.				
	BALLAST PUMP								
	MAIN BILGE LINE PUMPS								
	GENERAL SERVICE PUMP								
	EMERGENCY BILGE PUMP								
	SANITARY PUMP								
	CIRC. SEA WATER PUMPS								
	CIRC. FRESH WATER PUMPS								
	AIR COMPRESSOR								
	FRESH WATER PUMP								
	ENGINE TURNING GEAR								
	ENGINE REVERSING GEAR								
	LUBRICATING OIL PUMPS								
	OIL FUEL TRANSFER PUMP								
	WINDLASS								
	WINCHES, FORWARD								
	WINCHES, AFT								
	STEERING GEAR								
	(a) MOTOR GENERATOR								
	(b) MAIN MOTOR								
	WORKSHOP MOTOR								
	VENTILATING FANS								

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

p. pro. THE SUNDERLAND FORGE & ENGINEERING CO. LTD.

H. Haffes
 Electrical Engineers.

Date *22/8/29.*

COMPASSES.

Distance between electric generators or motors and standard compass *130 FEET*

Distance between electric generators or motors and steering compass *125 FEET.*

The nearest cables to the compasses are as follows:—

A cable carrying *3.4* Ampères *6* feet from standard compass *8* feet from steering compass.

A cable carrying *0.18* Ampères *6* feet from standard compass *LEAD INTO* ~~feet from~~ steering compass.

A cable carrying *0.18* Ampères *LEAD INTO ROOM* standard compass *6* feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *Yes*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted *Yes*

The maximum deviation due to electric currents was found to be *nil* degrees on *all* course in the case of the standard compass, and *nil* degrees on *all* course in the case of the steering compass.

For **SHORT BROTHERS LIMITED**

Ernest W. Short
 SECRETARY.

Builder's Signature.

Date *24th. Aug. 1929.*

Is this installation a duplicate of a previous case *no* If so, state name of vessel *—*

General Remarks (State quality of workmanship, opinions as to class, &c.)

The above installation is in accordance with the Society's Rules. The vessel is eligible in my opinion for notation elec light unless

It is submitted that
 this vessel is eligible for
 THE REGISTRATION OF
 ELEC. LIGHT

W.T. Badger
 Surveyor to Lloyd's Register of Shipping.

2/9/29.

Total Capacity of Generators *10* Kilowatts.

The amount of Fee	£ 10 : 0 :	When applied for, <i>Aug. 8th 1929.</i>
Travelling Expenses (if any) £	✓ : ✓ :	When received, <i>Aug. 19th 1929.</i>

W.T. Badger

Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

Elec Light

Im. 228.—Transfer.
 (The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2020

Lloyd's Register Foundation