

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.

Ref:- WR/HL.
Electrical Dept.

30th June, 1938.

Dear Sirs,

E.

Your Yard Nos. 283 and 300.
Pump Room Fittings.

I beg to acknowledge the receipt of your letter of the 25th instant relating to the provision of ventilating holes in the steel casing which surrounds the pump room fitting on the deck of the above vessels, and have to say that your remarks in the matter have been carefully noted.

In reply I have to inform you that owing to the breathing which will occur due to alternate heating and cooling, it is necessary to prevent explosive vapour from the pump room entering the interior of the box, and to ensure that the breathing takes place to the air on deck. In these circumstances it is considered that ventilating arrangements of the box should be made to provide free access of air from the deck. The nature and disposition of these arrangements should be such as to preclude the ingress of water.

I may add it is agreed that the radiating surface of the box is of ample capacity to

© 2019
Lloyd's Register
Foundation
W120-0237(1/2)

COPY.

Pump Room Fittings.

-2-

dissipate the heat developed by the 150 watt lamp.

I am, Dear Sirs,

Yours faithfully,

Secretary.

Messrs. Furness Shipbuilding Co. Ltd.,
Haverton Hill-on-Tees,
Billington,
Co. Durham.



© 2019

Lloyd's Register
Foundation

w120-0237(2/2)