

W1215-0020

s.s. "KOEPIA"
(Number 74488 in R.B.)

It is submitted the Naples Surveyors be informed as follows with regard to the alterations and additions proposed to this ship for classification, :-

(1) One web frame should be fitted in the machinery space each side as previously required on account of the deficiency of the scantlings of the side framing. The ends of the side bunkers could not be accepted as equivalent to this web frame as these are too far from the mid length of the machinery space.

(2) On account of the considerable deficiency of the second deck beams additional support must be provided by means of additional girders and pillars as previously required.

(3) The drillings of the strakes of shell plating above the waterline from the upper deck sheerstrake to the fourth strake below the same are generally satisfactory: the plating for the half length amidships should be renewed wherever it falls below the following thicknesses :-

Upper	Upper deck sheerstrake18 m/m
Strake below	" " "11½ m/m
2nd, 3rd & 4th strakes	" " "12½ m/m

3/16 + 7/16
used 14/11
3 plans

12/14/11

© 2020
Lloyd's Register
Foundation
11.11.24

ing
wa:
s
gine

as.
old
sis