

FRAMING.

PILLARS.

"ORMUZ"
S.S. "ORMUZ" ex "ZEPPELIN"
- Equipment Number 65,500

The equipment on board this ex-German vessel is given in the following Table, and the Rule requirements are given for comparison.

ANCHORS	Rule			On Board as reported.		
	cwt	qr.	lbs.	Cwt.	qr.	lbs.
1 Bower	103	2	19	1 Bower	123	3 7
1 Bower	103	2	19	1 Bower	115	3 21
1 Bower	103	2	18	1 Bower	113	2 18
Collective weight	311	0	0	353	1	18
Ex						
1 Stream	32	2	0	1 Stream	20	2 0 ex stock.
No kedje required.				1 Kedje.	9	3 4 ex stock.

CHAIN CABLE

330 Fms. 2-14/16 steel chain cable 315 fms. 3" Stud chain cable.
Weight 1378-cwts. weight 1467 cwts.
120 Fms. 1-10/16 stream chain
or 6" steel wire. (90 fms. 6" steel wire.
(45 fms. 14" coir.

TOW LINE

130 Fms. - 7" steel wire

(1-90 fms 5" steel wire.
(2-90 fms 4" " "
(4-90 fms 3 3/4" " "

HAWSERS & WARPS

4 of 120 fms 8" manila or 2 3/4" steel wire | 4 of 120 fms 9" Manila.

The anchors and chains have been properly tested and it is submitted in view of the collective weight of anchors and cables being so much in excess of the Rule Requirements the equipment supplied is favourably recommended for the consideration of the Committee for the figure '1'.

FRI. 18 AUG. 1922

approved.
Subject to
a stream anchor of
proper weight being supplied

© RML
17.8.22

Lloyd's Register
Foundation