

F.E.

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

VESSEL'S NAME Steel S.S. "Throckley" Rpt. Mdb. No. 11751

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

(The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement.—Extract from Sub-Committee's Report, 24/5/92.)

^{1st Longl.}
Transverse No. 6704

Depth "d" 18.95' to upper dk
20.7' " R.G. dk.

between
Framing Tables Nos 243

Description Built angle.

^{2nd} Longitudinal No. 20474

Proportions $\frac{\text{Length}}{\text{Depth}} = \frac{12.61}{1}$ to upper dk.

Deck Sheerstrake as approved.

This vessel has been built in accordance with the Revised Rules, and the Builders obtained the Owners' sanction thereto.

Damage sustained through striking dock wall now repaired as follows: Vessel placed in drydock, 1 shell plate removed, faired and refitted, 1 faired in place, and minor repairs effected.

This vessel appears to have been built in accordance with the Revised Rules and the approved plans, and it is submitted she is eligible to be classed **✱ 100. A. 1. (Steel)** "with freeboard," as recommended. The Summer freeboard of 5'-3" from centre of disc to top of statutory deck line at Upper deck, now marked on the vessel's sides, to be inserted in the classification certificate, and recorded in the Register Book, and further, the remaining freeboards, as shown on the accompanying verification form to be inserted in the certificate of classification.


✱ 100. A. 1 (Steel) "with freeboard."

1 dk (Stl) "well dk."

Cell DB uE 20', f 126' 432t, D. Ta 86' 799t, FPT 79t, ART 96t, FK, GBH, pt. Cem, Lloyds A+CP, Q 122', B56', F25'

The Certificate of Classification, to be stamped "Cargo buttons not fitted," and the same notation to be entered in the Register Book.

P.T.O.



Ad's Register Foundation
22/12/23.