


Princess Marguerite
Glasgow Dept 44501

SPARE GEAR FOR ENGINES AND BOILERS.

- 1 Spare tail shaft for Port shaft. ✓
- 1 spare tail shaft for Starboard shaft. ✓
- 1 full set of coupling bolts of each size fitted. ✓
- 12 pads for thrust block. ✓
- Full set of propeller blades for each propeller.
- 1 spare propeller boss with nuts and studs complete, right hand for No. 504.
- 1 spare propeller boss with nuts and studs complete, left hand for No. 505.
- 2 springs for safety valves of Scotch Marine boilers.
- 2 springs for safety valves of Yarrow boilers.
- 342 plain and 126 stay tubes for cylindrical boilers.
- 98 tubes 1.1/2" dia. x 10 W.G
- 662 tubes 1.1/4" dia. x 11 W.G. for W.T. Boilers.
- 100 Air heating tubes.
- 1 complete set of boiler door joints for all boilers.
- 48 gauge glasses, and approved washers.
- 6 doz. Dewrances hexagonal washers.
- 1 spare combined check valve, 1 main and 1 auxiliary.
- All bunker doors, etc. complete.
- A shuttle and valves for every Weir's Pump. ✓
- 1 spare crosshead and 1 bottom end for all pumps.
- 1 spare set of valves for all pumps, both suction and delivery. ✓
- Turbine blading - one fortieth of each size fitted (complete).
- 1 set of brasses for H.P. rotor bearings. ✓
- H.P. Aft gland 8 rectangular carbon rings and 8 Spiral springs.
- 1 set of brasses for L.P. rotor bearings. ✓
- H.P. Ford. gland 6 angular carbon rings and 6 spiral springs. ✓
- 1 complete set of gland rings and springs. ✓
- H.P. Ford gland 4 rectangular carbon rings and 4 spiral springs. ✓



W124-02513

- 3 -

ELECTRIC FANS.-

1 armature, 1 set of brushes and gear, 1 set of field coils for each size of motor.

OIL FUEL SPARE.-

1 complete set of heater coils and covers, or as required, to suit installation.

2 complete sets of strainers for suction, delivery and burners.

1 complete set of thermometers.

13 spare burners with tips complete.

100 spare tips of smallest size in addition to 6 spares to each other size.

Quantity of assorted bolts studs and nuts, Bars and Plates of iron or mild steel.



© 2021

Lloyd's Register
Foundation

W1224-0251 3/3