

No. of Bilge pumps 2 Diameter of ditto 4 1/4" Stroke 24" Can one be overhauled while the other is at work
Size of Pumps 10" x 10" x 10" 7 1/2" x 5" x 6" No. and size of Suctions connected to boiler

Urgent.

s/s Birma.

New Rpt N° 61988.

It is submitted, that the Newcastle Surveyors should be requested to state by wire, whether they are correct in stating ~~that~~ that the diameter of the propeller is 18 feet, as this with no liners on the screw shaft would ^{requiring} ~~necessitate~~ the screw shaft being 15.39" dia^d by The Rules. instead of 15" as stated on the report.

Lr: - 25/3/12

© 2021 Lloyd's Register Foundation
W/225-0177

Smallest distance between boilers or uptakes and bunkers or woodwork
Thickness 1 9/32" Range of tensile strength 29-32 1/2 tons Are the shell plates welded or flanged no Descrip. of riveting
seams 7 x 1/4" Diameter of rivets 1 1/4" x 1 1/4"