

REPORT of SURVEY for REPAIRS

Date of writing Report 20th May 1930 When handed in at Local Office 19

Port of Hamburg

No. in Reg. Book. 63473/13777

Survey held at Hamburg

Date, First Survey 13th May 1930

(No. of Visits 3)

on the Wood, Iron or Steel *IRON* "ANDIJK" in Rotterdam

TONNAGE

Built at Newcastle

By whom *W. H. M. M. L. S. B. Co. Ltd.*

GROSS 6292

Owners *Holland-Amerika Stoom Maats.*

Owners' Address

UNDER DEK 6108

Managers *(Holland Amerika Lijn)*

Port belonging to Rotterdam

NET 4037

Surveyed Afloat or in Dry Dock? *afloat* Name of Dock *harbour*Destined Voyage *Rotterdam*B=Cell D=Bor D=Ba feet; uE&B feet; f feet
al capacity tons. FPT tons; APT tons; MT feet tons.

N.B.—All alterations in the existing records should be underlined.

If the Vessel has Water Ballast Tanks, state whether the manhole covers have been removed, and the insides of tanks examined. Also state the amount of deterioration (if any) found in the thicknesses of the floors, framing, and of the inner bottom plating, especially in the boiler space.

Last Report, No. 19422 Port *Rot.*

Particulars of Classification (which must be precisely as in Register Book & Supplements).

| CHARACTER. | Year of last Survey and of Periodical Surveys. | Machinery and Boiler Surveys (including date of N.D., if any). |
|---------------------------|--|--|
| + 100 A 1. | | + LMC |
| Shelter dk with preboard. | | MS. 3.26 |
| 6.29. | | MS. 1.30 |
| SS. Ref. No. 3-9.21. | | BS. 1.30. |
| SS. Ref. No. 1-26. | | T.S. seen 3.29. |
| | | (CL.) |

Society's Freeboard (if assigned) as painted on Ship and now verified *K fl. V 378.*

Certificate attached.

Was a damage report made by anyone else? If so, by whom? *V*PAIRS, OR EXAMINATION AS PER RULE, FOR *Condition afloat + damage repairs:*

The vessel surveyed afloat, found decks, hatchways, hatches, ventilators + coamings on deck satisfactory. Masting gear + connections also windlass examined, found in good working order.

Damage repairs now done: Damage stated to have been sustained through heavy weather during the voyage from Cran to Antwerp in April 1930.

Starboard side in 7th stoke below sheer stoke plate No. 3 from aft renewed and the same on port side repaired by fitting an efficient riveted doubling plate for 3 frame spaces length and full breadth of stoke abait fore butt. - Topped repairs on completion and found now tight and recoated in good order.

It was stated by the Captain that the Spec. Surv. No. 2 will be carried out at Rotterdam.

RY OF DAMAGE REPAIRS:—

| | Shell Plates. | Frames. | R. Frames. | Floors. | Beams. | Str. Plates. | Dk. Plates. | Other Items:— |
|--------------------------------|---------------|----------|------------|----------|----------|--------------|-------------|---------------|
| Renewed | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> |
| Removed and Faired or Repaired | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> |
| Faired or Repaired in place | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> | <i>V</i> |

T CONDITION OF THE

| | | | |
|--------------------------------|---|--|---|
| Decks <i>Good.</i> | State if Tanks have been examined inside <i>no</i> | Dblg. Plates under Sounding Pipes <i>V</i> | Copper, or Y.M. of Wood Vessels (State if on Felt). When put on, Month Year |
| Fastenings <i>V</i> | State if Tanks now tested <i>no</i> | Engine Room Skylights <i>Good.</i> | Boats <i>Good.</i> |
| Plating <i>where seen good</i> | Bulkheads <i>where seen good</i> | Coal Bunkers, Open'gs, Lids, &c. <i>"</i> | Masts, Yards, &c. <i>"</i> |
| Frames <i>V</i> | Ceiling <i>V</i> | Scuppers <i>"</i> | Condition, how ascertained <i>pr. dk.</i> |
| Plating <i>where seen good</i> | Cement or Asphalt (State which.) <i>V</i> | Cargo Hatchways <i>"</i> | (State if wedges removed) <i>V</i> |
| Frames <i>V</i> | Rudder <i>V</i> | Hatches <i>"</i> | Sails <i>V</i> |
| Plating <i>where seen good</i> | Steering gear and its connections <i>Good</i> | Planing of Wood Vessels <i>"</i> | Equipment letter <i>A+</i> |
| Frames <i>V</i> | Windlass <i>"</i> | Caulking ditto | Anchors, No. of <i>3 B. 15. 1K.</i> |
| Plating <i>where seen good</i> | Have Pumps now been examined and found efficient? <i>V</i> | Treenails ditto | Cables (State if now ranged) <i>no</i> |
| Frames <i>V</i> | Have Sluice Valves now been examined and found efficient? <i>V</i> | Breasthooks & Stemson ditto | length <i>stated complete</i> |
| Plating <i>where seen good</i> | Have Watertight Doors now been examined and found efficient? <i>V</i> | Transoms, Pointers, & Crutches ditto | Rule length <i>V</i> size <i>V</i> |
| Frames <i>V</i> | Have Ventilators and their Coamings been examined and found efficient? <i>yes</i> | Timbers of Frame at openings ditto | Hawser & Warps <i>Good.</i> |
| Plating <i>where seen good</i> | | Ditto ditto at other places ditto | Standing and Running Rigging <i>Good.</i> |
| Frames <i>V</i> | | Stringers, Clamps & Shelves ditto | |
| Plating <i>where seen good</i> | | Salting (State if examined.) ditto | |

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon survey, thus, for example:— "to remain as now classed in the Register Book without fresh record of Survey," "to remain as classed and to have record of survey 1.24," or "to remain as classed and to have record of survey, 1.24, and the notations of ss No. 1-24 and ptd 24, &c."

The vessel appears, as far as seen, to be in a sound and efficient condition, eligible in opinion to remain as classed in the Society's Register Book without fresh record of survey.

| | | | |
|---------------------------------|---|----|-----------------------------|
| (per Section 29) £ | : | : | Fees applied for, 20-5-1930 |
| Damage or Repair Fee (if any) £ | 4 | 70 | Received by me. 19 |
| Expenses (if chargeable) £ | - | 75 | |
| Surveyor's Fee (if any) £ | - | - | |

Committee's Minute

Character Assigned

FRI. 30 MAY 1930

Referred for No 2

Friedrich Ohlgen.
Surveyor to Lloyd's Register of Shipping.

General Committee.

Thursday 19th March 1930

Classing Committee

decision and find

Alan 19/3/31

To Certificate required? If so, to be sent to

W1242-0163