

Confirmation
COPY for Shanghai

LLOYD'S REGISTER OF SHIPPING

MEIKAI BUILDING

No. 32, AKASHI MACHI,

TELEGRAMS: "REGISTER" KOBE
TELEPHONE:- 2530 SANNOMIYA

KOBE, 17th February, 1926.

The Surveyors.

...SHANGHAI.

Dear Sirs:

Shanghai Dock & Eng. Co's
Boilore Nos. 1727-1728
for Pilet Boat
Bull No. 1725

In answer to your letter of the 6th inst forwarding
Dwg. No. 25/26 in quadruplicate for approval. I have to
acquaint you that the design as shown and amended on the plan
would be approved for the intended working pressure of 180 lbs.
per sq.inch provided the following condition be complied with,
viz.

- (1) Riveting of manhole compensation plate.
(a) centre rivets at ends to be omitted.
(b) pitch of end rivets to be .8".
- (2) Furnace thicknesses (not stated in plan)
to be suitable for 180 lbs. W.P.
- (3) Marginal stay tubes to have $\frac{1}{4}$ " minimum
thickness at bottom of thread - as
required by Sect. 30, clause 5. say $\frac{3}{8}$ thick.
- (4) Two additional stay tubes to be fitted at
at the lower wings.
at the lower wings



(a)

(5) Materials used in the construction
to be made & tested at approved
works.

(6) Boilers to be constructed under the
usual conditions of survey &
testing.

Two copies of the approved plan are being returned
under separate cover.

I am, dear Sirs,

Yours faithfully,

Rulatt



© 2020

Lloyd's Register
W1249-0224
Foundation