

\$ 96.00

Jacksonville, Fla.,

21st May 1926.

HUGH BOYLE

Mr. J. F. O'Boyle, Owner, survey the Steel Barge *NAVIGADORA 77* for the purpose of ascertaining the nature and extent of damage vessels having put into Jacksonville, Fla., in distress on the 30th April while on a voyage from Tampico to New York in tow of Tug *GOLIAN*.

For further particulars see Log Book and Protest.

An examination of the vessel while lying afloat at Jacksonville Fla., on the 31st April 1926 found vessel had five feet four inches of water in tanks. Vessel was sounded four hours later and found to be making no water. Recommended that water be pumped out and soundings taken. Vessel was pumped out and sounding taken at four, twentyfour and fortyeight hours and found to be making no water.

Vessel was placed on dry dock for examination and filled with water for testing and found 600 rivets and about 200 feet of seam leaking badly.

RECOMMENDED:- That tanks be cleaned, approximately 600 rivets be renewed and 200 feet of seam chipped and caulked. On test rivets totalled 1139 and several more feet of seam. It was further recommended that these rivets be renewed and all leaky seams made tight.

The above recommendations were made with the view of placing the vessel in the same good condition as before the above sea damage occurred.

FEE & EXPENSES. \$ 56.50

Hugh Boyle



© 2020

Lloyd's Register
Foundation

W1250-0039