

S.S. "TROJA"

The Thor Iron Works No. 5.

Plans for this vessel were approved 28-11-16, by Mr. French.

The First Entry Report on the Vessel is now to hand, and it is found the length has been increased by 3" and the depth by $1\frac{1}{4}$ " over the dimensions shown on the plan.

Amended Dimensions: 251.25 x 43.5 x 28.27 to Upper Deck.

35.29 to Bridge Deck.

Scantling Numbers: 71.77 and 18032.

Proportions: Length to Depth - under 10.

The increased dimensions of the vessel involve a change of grade in the plating number. The double bottom thus is 1" less in depth and the tank top .02 in thickness than required by the Rules.

Suitable compensation in the form of increased thickness of shell plating &c. is provided.

It is submitted that the scantlings are such as could be accepted for the 100 A.1 Class.

C.F.
12. 8. 18.



© 2020

Lloyd's Register
Foundation

R.M.M.

W1251-0175

Mr Warren