

COPY.

Lloyd's Register of Shipping,

71, Fenchurch Street, E.C. 3.

1 Enclosure.

28th June, 1921.

Dear Sirs,

I duly received Mr. Roberts' letter of the 16th instant submitting for the consideration of the Committee a plan, in duplicate, of superheaters proposed for Messrs. Bacini & Scali Napoletani's S.S.No.C.B.12, and with regard thereto I have to acquaint you that provided the cast steel chests on examination be found sound and free from defects; the method of attaching the tubes to the chests be to your satisfaction; a safety valve be fitted to every portion of the superheater which can be shut off from the boiler, and the whole be tested hydraulically to 3 times the working pressure, viz:- 39 atmospheres (555 lbs per square inch), the same will be approved by the Committee for a working pressure of 13 atmospheres (185 lbs per square inch).

One copy of the plan forwarded is returned herewith, and the duplicate copy is being retained in this Office for reference.

I am, Dear Sirs,
Yours faithfully,

The Surveyors,
NAPLES.

W1265-0055

© 2020

Lloyd's Register
Secretary.
Foundation