

COPY.



of NAPLES

1st, July 1921

W. H. ROBERTS,

the Bacini & Scali Napoletani did examine the machinery and boilers of their C.B.12 named "GIULIA PIERCE" on the 7th May 1921 and subsequent dates with a view to Classification, and that I have transmitted to the Committee to Lloyd's Register of Shipping London a Report stating that I have Recommended that the vessels machinery be eligible in my opinion for notation of L.M.C. with date when the following items have been carried out.

- 1) Boilers and Superheaters to test to 328 lbs. "
- 2) H.P. M.P. & L.P. pistons and slide valves to examine.
- 3) Crank Shaft and bearings to examine.
- 4) If drawings of Superheaters are approved.
safety valves and easing gear to fit.
- 5) Main boiler safety valves to adjust to 185 lbs "(13 atmos)
- 6) Safety valves when fitted to Superheaters to adjust to slightly higher pressure than main boilers.
- 7) Drawing of Donkey boiler to submit for approval, or Committee may accept Marks of EC test.
- 8) Donkey boiler to test to 200 lbs "
- 9) Safety valves of donkey boiler to adjust to 100 lbs "

W. H. Roberts

Surveyor to Lloyds Register of Shipping

Via A. Depretis No. 31

Naples

Items to test
lbs See Lon

3/6/21 T
letter 2/7/21



© 2020

Lloyd's Register
Foundation

W1265-0063