

"SAN JERONIMO".

Whale Oil Apparatus.

IT IS SUBMITTED the plan of extractor merits approval for a working pressure of 3 kg. per sq. cm., provided the diameter of the rivet holes be 20 mm., the thickness of the dished end plates be not less than 10 mm., and the internal radius of the same plates not greater than 2000 mm., the dimensions of the dome compensating plates and the dome covers meet the requirements of the Rules for the Construction of Boilers for the intended working pressure, and the extractors be constructed under the usual conditions of survey and testing.

Particulars of the dome compensation plates and covers, and the method of securing the dome covers should be forwarded for consideration.

Return plan.

Retain copy.

9.5.28.

L 10/5/28



© 2019

Lloyd's Register
Foundation

W127-0147