

COPY.

Translation of cablegram sent Oslo 30. 5. 28.

Southern Empress
Myrens Verksted
whale oil

- ✓ Iheik - boilers
- ✓ Junnu - plans
- ✓ Kywho - approved
- ✓ Lisyh - for
- ✓ Ijkub - working pressure
- ✓ Onkyx - 80 lb. per sq.in.
- ✓ Marki - provided
- ✓ Letyd - diameter
- ✓ Icudo - rivet
- ✓ Loluf - holes
- ✓ Lotah - in
- ✓ Luxge - longitudinal
- ✓ Kyusc - and
- ✓ LecwO - circumferential
- ✓ Ideyx - seams
- ✓ Lyord - not less than
- ✓ Olvuc - 20
- ✓ Omolm - mm.
- ✓ Kyusc - and
- ✓ Lyog^N - not greater than
- ✓ Olwib - 24
- ✓ Omolm - mm.
- ✓ Miroj - thickness of
- ✓ Miwak - top
- ✓ Kyusc - and
- ✓ Latar - bottom
dished
- ✓ Ijviv - end plates
- ✓ Lyord - not less than
- ✓ Olwoo - 25
- ✓ Omolm - mm.
- ✓ Kyusc - and
- ✓ Olwax - 22
- ✓ Omolm - mm.
- ✓ Melki - respectively
- ✓ Lyxaw - or
- ✓ Kyuch - alternatively
- ✓ Lybod - material
- ✓ Lythe - of
dished
- ✓ Ijviv - end plates
- ✓ Lojaw - have
- ✓ Kubhu - tensile strength



© 2019

Lloyd's Register
Foundation

W127-0174 (1/2)

COPY.

-2-

- ✓ Lythe - of
- ✓ Lyord - not less than
- ✓ Olzof - 43
- ✓ Ohjat - .5
- ✓ Omme - kg/mm²
- ✓ Kyuso - and
- ✓ Lyowl - not more than
- ✓ Olzto - 47
- ✓ Omme - kg/mm²
- ✓ Koxym - steel castings
- ✓ Misxo - to be
- ✓ Luyhr - made
- ✓ Lahte - at
- ✓ Koxeh - Works recognised by Committee
- ✓ Kyuso - and
- ✓ Kryhd - tested
- ✓ Lourh - in accordance with Society's Rules.
- ✓ Kythy - also
- ✓ Mijno - subject to usual conditions
Jariso Vaerit
whale oil
- ✓ Theik - boilers
- ✓ Jummo - plan
- ✓ Kywho - approved
- ✓ Lisyh - for
- ✓ Ijkub - working pressure
- ✓ Omkyx - 80 lb. per sq. inch
- ✓ Mijno - subject to usual conditions



© 2019

Lloyd's Register
0177-0174 (2/2)
Foundation