

Lloyd's Register of Shipping,

(MEIKAI BUILDING)

32, AKASHI-MACHI,

KOBE, 18th June, 1928.


Cert. No. 1421.

This is to Certify that at the request of Messrs. The Kobe Steel Works, Limited, Kobe, the Open Hearth Steel ~~Forgings~~ or Castings named below ~~was~~ ^{were} examined and tested at their works on 23rd April, 5th May, 2nd & 7th June, 1928. and found to be as far as could be ascertained, sound and free from defect.

ONE STERN FRAME.

Weight 6360 Kilgs.

Drop tests: Dropped from a height of 8 feet on to the hard ground then suspended and hammered without indication of defect.
Drilling Tests:- Three Holes were drilled at "X" (See sketch), casting found good and holes filled with C.S.K. rivets.
Delivered in rough machined condition.

Test Mark	Tenacity Tons/sq in	Elongation % in 2"	Bend 1/4" x 1" x 120°	
B 2284 - 4	29.6	25	Good	
--	--	--	--	
--	--	--	--	
--	--	--	--	
--	--	--	--	

This Stern Frame is intended for Uraga Dockyard No. 329.

and ^{has} ~~have~~ been stamped as follows:-

Fee Yen) See
Expenses ,,) Debit
Note.

B 2284-4
LLOYD'S
DROP TEST
23-4-28
No. 1421
7-6-28
A.W. LR

A. W. L.

Surveyor to Lloyd's Register.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:--
"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society or for any error of judgment, default, or negligence of the Surveyors, other Officers or Agents of the Society."

Not
over

Lloyd's Register of Shipping

(MEIKAI BUILDING)

32, AKASHI-MACHI,

KOBE, 18th June, 1928.

Cert. No. 1421.

This is to Certify that at the request

Messrs. The Kobe Steel Works, Limited, Kobe.


the Open Hearth Steel Castings named below were examined and tested at their works on 27th April, 2nd & 7th June, 1928. and found to be as far as could be ascertained, sound and free from defect.

ONE STEEL FRAME.

Weight 6760 Kilos.

Drop tests: Dropped from a height of 8 feet on to the hard ground then unsuspended and hammered without indication of defect. Drilling Tests: Three Holes were drilled at "X" (See sketch). casting found good and holes filled with C.S.K. rivets. Delivered in rough machined condition.

Test Mark	Tensile Tons in	Elongation % in 2"	Bend 180°
B 2284 - 4	22.6	22	Good
--	--	--	--
--	--	--	--
--	--	--	--
--	--	--	--



This steel frame is intended for Uraga Dockyard No. 329.


and has been stamped as follows:-

B 2284-4
LLOYD'S
DROP TEST
27-4-28
No. 1421
7-6-28
A.W. 12

Expenses ()
Note. ()
Debit ()
Yen () See

Surveyor to Lloyd's Register.

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that: "While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors or in any entry in the Register Book or other publication of the Society or for any error of judgment, default or negligence of the Surveyors, other Officers or Agents of the Society."



Lloyd's Register
Foundation