

FOR THE
BRITISH TANKER CO LTD

SHIP № 1221

STERN POST 4" x 1 1/2" FLAT BAR. STEM 4" x 1" FLAT BAR.
 RUDDER - 5/16" PLATE 2 1/2" DIA STOCK

FRAMES: 12 IN HOLD 4" x 2 1/2" x 30" BULB ANGLES, SPACED

FRAMES: IN HOLD 4" x 12" x 30 DOUB ANGLE, SPACED
20" APART, TURNED & OVERLAPPED TO
FLOORS.

14 PEAKS $3 \times 2\frac{1}{2} \times 5/16$ ANGLES SPACED 20' APART.

FLOORS:-

REVERSE FRAMES: IN PEAKS $2\frac{1}{2}'' \times 2\frac{1}{2}'' \times 5/16''$ ANGLES.

BEAMS & HALF BEAMS:- $3" \times 2\frac{1}{2}" \times \frac{5}{16}"$ ON EVERY FRAME.

TANK SUPPORTS:- $\frac{1}{4}$ " PLATES STIFFENED WITH $2\frac{1}{2}$ " x $2\frac{1}{2}$ " x $\frac{5}{16}$ "

BULK HEADS:- TWO OIL TIGHT PLATES 4 STIFFS 3"x22"x7/16
ANGLES 30" APART. FRAMES 4"x4"x30" ANGLES

DRAWN BY *HL*
TRACED BY *HL*
CHECKED BY *HL*
DATE 11-13-31

PLAN No 18246

JAMES POLLOCK SONS & Co LTD
SHIPBUILDERS & ENGINEERS,
3, LLOYDS AVENUE,
LONDON, E.C.3.

Lloyd's Register Foundation

Pollock 1221

ms Prose Deeds

British Boy

London Report No. 90,241

RETAIN



© 2020

Lloyd's Register
Foundation

W1270-0149