

COPY.

Lloyd's Register of Shipping.

Port of P I R A E U S.

19th September, 1932.

This is to Certify that

A R T H U R W. O X F O R D

Designated Surveyor to this Society did at the request of
Saunders & Co., Lloyd's Agents, Salonica, and with the
consent of the Owner, attend on board the Steel Screw Steamer
"MOS COUTSODONTIS" of Syra, Greece, Gross Tons 3076,
entered in the Register Book, as she lay afloat near to the
Harbour of Salonica, on the 15th day of September 1932 to
inspect and report upon damage stated to have been sustained
by the vessel stranding on Europa Point on the 28th
May 1932, whilst on voyage from Cardiff to Salonica
laden with cargo of coal.

For further particulars see vessel's Log Book, Protest and the
Report of the Surveyor to the Salvage Association, London,
and report and recommend as follows :

P.T.O.

Chw.

and upon the terms of the Rules and Regulations of the Society, which provide that :—

The Society use their best endeavours to ensure that the functions of the Society are properly executed, it is
not the Committee nor the Society are under any circumstances whatever to be held responsible for
any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents

- 2 -

S.S. "STYLIANOS COUTSODONTIS".

<u>EXAMINATION FOUND.</u>	<u>RECOMMENDED.</u>
LD.	:
<u>BULKHEAD.</u>	:
DE.	:
stringer bracket to	: Remove, fair and refit.
and buckled.	: Approx. size: 4'0" x 2'6" x $\frac{1}{8}$ ".
bulkhead plate stiffener	: Remove, fair and refit.
	: Approx. size: 16'0" x 2'8" x $\frac{1}{8}$ "
	: flanged 3".
angle stiffener	: Remove, fair and refit.
	: Approx. size: 25'0" x 7" x $3\frac{1}{8}$ ".
<u>Head Plating.</u>	:
Plating is in vertical	:
and lettered from	:
(reporter's side).	:
Lower plate	: Remove, fair and refit.
	: Approx. size: 14'0" x 5'0" x $\frac{7}{20}$ ".
Lower plate	: Renew.
	: Approx. size: 11'6" x 5'0" x $\frac{7}{20}$ ".
<u>BOARD SIDE.</u>	:
stringer bracket to	: Remove, fair and refit.
and buckled.	: Approx. size: 4'0" x 2'6" x $\frac{1}{8}$ ".
bulkhead plate stiffener	: Remove, fair and refit.
	: Approx. size: 16'0" x 2'8" x $\frac{1}{8}$ "
	: flanged 3".
<u>Head Plating</u>	:
Lower plate	: Renew.
	: Approx. size: 11'6" x 5'0" x $\frac{7}{20}$ ".

P.T.O.

Lloyd's Register
Foundation

W1274-0225 43

S.S. "STYLIANOS GOUTSODONTIS".

<u>DAMAGE FOUND.</u>	<u>RECOMMENDED.</u>
- Lower plate	: Remove, fair and refit. : Approx. size: 14'0" x 5'0" x 7/20".
- Lower plate	: Renew. : Approx. size: 11'6" x 5'0" x 7/20".
- Lower plate	: Remove, fair and refit. : Approx. size: 14'0" x 5'0" x 7/20".
	:
pillars broken,	: Remove, repair and refit. : Approx. size: 25'0" x 4½" diam.
pillars bent.	: Remove, fair and refit. : Approx. size: 25'0" x 4½" diam.
ing board stanchion	: Renew. : Approx. size: One plate 12'0" x 9" x ½". : Four angles - 12'0" x 3" x 3".
ber boards damaged	: Renew approximately 240 running
l for examination.	: feet of 11" x 2½" planks.

rt only covers the foregoing damage found in Nos. 1 & 2
e vessel having been previously examined in dry dock
(condition) at Gibraltar by a Surveyor to the Salvage
on, London, and all damage found to bottom plating and
in tanks reported upon from that port.

as & Travelling
ence Expenses, to,
Salonica.

.O.O.

a pounds sterling).

Arthur W. Oxford.
Surveyor to Lloyd's Register.



© 2020

Lloyd's Register
Foundation

W1274-022513