

S. S. "ATLANTICOS" ex "SYLVIA VICTORIA"

Engines No. 558

Messrs. J.G. Kincaid & Co. Ltd.  
-----

The Greenock Surveyors have forwarded a letter from the Builders who state that owing to the limited time at their disposal for fitting the new machinery in the above vessel, they propose fitting a screw shaft which they have in stock, and they desire to know if the proposal will be accepted. The material of the shaft has been tested by the Surveyors to this Society.


The proposed size of the screw shaft viz:- 15" diameter meets the requirements of the Rules with the exception of the diameter of the shaft in way of coupling, which is slightly below the Rule size of 13.825" against 14.09".

IT IS SUBMITTED that with steam reciprocating engines having cylinders 27" x 44" x 73" by 48" stroke (working pressure 185 lbs per square inch, diameter of propeller 17' 6" and screw shaft fitted with a continuous liner the size of the screw shaft viz:- 15" diameter and 13.875 at the coupling might be approved in this instance.

*J.M.H.*

*J.G.K.*  
*C.M.S.*  
1. 9. 22.

*L 1/9/22*



© 2021

Lloyd's Register  
Foundation

W1310-0141

2. Assigned + LMC 11.22

Note shaft.

MAY 1