

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping  
 gnal Letters (if any) L.H.B.P.

Official Number.	Name of Ship.	No., Date, and Port of Registry.	
161,876.	Corabank.	4 in 1931 Belfast.	
Initial Registry.			
Date, and Port of Previous Registry (if any).	Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Name and Address of Builders.
	British	Motor Ship Single Screw.	Workman Clark (1928) Ltd., Belfast.
Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet. 477 Tenth. 0.
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	477 0.
rigged ...	Schooner	Main breadth to outside of plank ...	63 8.
tern ...	Round	Depth in hold from tonnage deck to ceiling at midships ...	35 6.5
uild ...	Clencher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	--- ---
alleries ...	None	Depth from top of beam amidships to top of keel ...	36 6.7
ead ...	None	Depth from top of deck at side amidships to bottom of keel ...	35 5.7
ramework and description of	Steel	Round of beam ...	1 3.3
vessel ...	Oil Carrier	Length of engine room, if any ...	62 6.0
umber of Bulkheads ...	18		
umber of water ballast tanks, 6, 1237.			
and their capacity in tons ...			

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 17621 Tons. Ditto per inch immersion at same depth ... 60.0 Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B.H.P. I. H. P. Speed of Ship.
				No. and Diameter of Cylinders in each set.	Length of Stroke.		
Vertical Sulzer type Internal Combustion	Engines. British	Engines. 1931	Engines. Workman Clark (1928) Ltd., Belfast.	26 3/4"	47 1/4"		994
Particulars of Boilers.	Boilers.	Boilers.	Boilers.	680 m/m	1200 m/m	8	3000
Description ...							3950
Number ...							12 knots
Iron or Steel ...							
Loaded Pressure ...							

## PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	8146.42	On account of space required for propelling power	2847.42
Space or spaces between Decks ...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	371.39
Turret or Trunk ...	29.08	These spaces are the following, viz:—	
Recastle ... Houses ...	40.05	Round Houses, Poop, Bridge.	
Edge space Houses ...	246.26	(Number of Seamen or Apprentices for whom accommodation is certified ... 48 ...)	
Open or Break ...	242.11		
le Houses ...	5.46		
ck Houses ...			
art House ...			
aces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	188.82	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
ccess of Hatchways ...	nil.	Masters Accomdn. 22.49	
		Chart Space 5.46	
		Wireless Tel Space 4.70	
		Boatswain's Stores 68.63	
		Pump Room 25.52	
		Cofferdam Space 111.73	
		Water Ballast Spaces 65.34	
Gross Tonnage ...	8898.20		
Deductions, as per Contra ...	3532.62		
Register Tonnage ...	5365.58		

RE 1.—The tonnage of the engine room spaces below the Upper Deck is 892.96 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 230.27 tons.

RE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Spaces:— Ecle Length 40.4 ft.— 55.05 tons.  
 Bridge — Length 33.0 ft.— 108.80 tons.

Name of Master

Certificate of { Service No.  
Competency No.

of Owners

ame, Residence, and Description of Managing Owner if there are more owners than one.

The Bank Line Limited  
 102, Hope Street, Glasgow.  
 Sixty-four (64) Shares.

Hon. Andrew Alexander Morton Weir  
 same address—Manager—

ated 27th April 1931.

(12) Wt. 2855/169 Gp. 144 2000 5-29 W &amp; S Ltd.

Lloyd's Register  
 Foundation

W1312-0183