

7.9.23

S.S. "SIR JAMES CLARK ROSS" ex "MAHRONDA".

VAERKSTEDT

A letter has been received from FRAMNAES pr SANDIF JOED Framnaes Mek.

Marksted who are altering this vessel for the purpose of
SIR JAMES CLARK ROSS PROPOSAL REGARDING HATCHWAYS APPROVED
PROVIDED STEEL WATERTIGHT HATCH COVERS BE FITTED

It is proposed to fit 3 trimming hatches on the upper
deck aft, on each side, and one COMMITTEE. side of the upper deck
forward, each hatchway being 4 feet by 4 feet.

They request that these coamings may be approved 9" in
height above the upper deck, *instead of 12" as required by the Rules* as a greater height of coaming will
render the whaling work on deck difficult.

On the plans forwarded wood covers are indicated.

It is submitted that, as the proposals are made to suit
the Owners' special trade, they might be approved in whole
in substance, provided the hatchway coamings be formed as indicated
on the plan and steel kinged and bolted with covers

be fitted in place of the wood covers.



© 2020

Lloyd's Register
Foundation

W133-0218