

[illegible]

GENERAL REMARKS—(continued).

PARTICULARS FOR RECORD in the REGISTER BOOK.—Length of Poop *24.16* ft., R.Q.D. *90.08* ft., Bridge *52.87* ft., Forecastle *30.33* (in feet and tenths). When the Poop is joined to the B.D., this should be distinctly stated *joined by raised quarter deck.*

No. and Material of Decks (if Iron or Steel) and whether wholly or partially covered with wood, and No. of tiers of Beams (this information is to be given as should appear in the Register Book) *1 D⁴ (541) Intermediate bulk head in fore hold dispensed with* *H.B.H. only* *L.A. & C.P.*

Official No. *129330*; Signal Letters. State if Machinery is fitted aft *no.*
How are the surfaces preserved from oxidation? Inside *"Siderosthen", paint, portland cement* Outside *paint.*

PARTICULARS OF WATER BALLAST.—State whether the Double bottom is constructed on the cellular system or with girders on floors *Cellular System*

Where Fitted.	*Length. Feet.	Water Capacity. Tons.	Where Fitted.	*Length. Feet.	Water Capacity. Tons.
Double bottom, aft, <i>and extending 21.54 ft under engines = 63 tons.</i>	<i>107.7</i>	<i>207</i>	Fore peak tank.		
Double bottom, under Engines and Boilers <i>{ included in after tanks. }</i>			After peak tank.		<i>97</i>
Double bottom, if under Engines only.			Deep tank, aft.		
Double bottom, if under Boilers only.			Deep tank, forward.		
Double bottom, forward.	<i>115.54</i>	<i>290</i>	Other tanks, if fitted.		
Total capacity of double bottom		<i>497</i>	(If necessary, furnish further information by sketch.)		

* The wells are not to be included in the lengths of the tanks.

State whether the above have been tested as required by the Rules *yes.*

Order for Special Survey No. *5018*

Date *20-2-12*

No. *149* in builder's yard.

DATES of Surveys held while building

1912 Sept 24. Feb. 10. 12. 17. 21. 25. 28. Mar. 3. 4. 10. 12. 13. 18. 19. 26. 28. 29. Apr. 4. 7. 10. 15. 22. 25. 30. May 5. 22. 23. 28. Jun. 4. 5. 12. 16. 18. Jul. 3. 4. 11. 12. 16. 23. 29. Aug 1.

Total No. of Visits *43.*

Surveyor's Signature *Amundsen*

Lloyd's Register Foundation