


COPY



LLOYD'S REGISTER

LONDON

REC-  
1000

81 JUL 1922

Hong Kong

June 6th. 1922.

This is to Certify that

JOHN S. GARDNER

Designated Surveyor to this

Survey

The Owners' Representative, survey for the computation of the Deadweight of the British Screw Steamer "PLEIADON" of Hong Kong, 5818.86 Tons Gross, built by the Hong Kong & Whampoa Dock Company Limited.

From the particulars supplied by the builders and the information obtained by the undersigned when this vessel was afloat on May 25th. 1922 in Kowloon Dock, the following figures are the result of this investigation:-

Vessel afloat in Kowloon Dock.

Draft Forward	2'-6 $\frac{1}{4}$ "	Mean Draft	9'-4 $\frac{1}{2}$ "
Draft Aft	16'-3"		

Corresponding Displacement in Salt Water = 3996 Tons

Items to be added or deducted to complete vessel

	<u>Tons to be added</u>	<u>Tons to be deducted</u>
Men	-	2
Rubbish	-	10
Oil for Donkey Boiler	-	4
Water in Donkey Boiler	-	13
Crank Shafts	-	10 $\frac{1}{2}$
Mooring wires	-	1
		<hr/>
		40

Carried over



© 2021

Lloyd's Register  
Foundation

W1337-0182-12



S. S. "PLEIADON"

( 2 )

	<u>Tons to be added</u>	<u>Tons to be deducted</u>	
Brought Forward	-	40	
Water in aft peak tank	-	87	
Ashes & rubbish in Stoksheld	-	2	
Spare Propeller	-	9	
Sundries (Including Engineers' Tools)	-	7	
Pipes to complete	5	-	
	<hr/>	<hr/>	
	5	145	
		5	
		<hr/>	
Total weight to be deducted		140	Tons
		3996	Tons
		<hr/>	
Finished light weight		3856	Tons
Load Displacement on Lloyd's Summer Freshboard	6'-9 $\frac{1}{2}$ "		)
Load Draft Bottom of Keel	24'-8 $\frac{1}{2}$ "		)
		12179	)
		<hr/>	
Actual Salt Water Deadweight		8323	Tons

Survey fee - - - - - \$400.00

John. S. Gardner

Surveyor to Lloyd's Register



© 2021  
Lloyd's Register  
Foundation

0182 12





"PLINION"

( 2 )

Tons to be added		Tons to be deducted	
Brought Forward		40	
Water in oil tank		87	
Ashes & rubbish in storeroom		3	
Spare Propeller		9	
Bundles (including		7	
Enginero's Tools)		-	
Pipes to complete		-	
5		148	
8		-	
Total weight to be deducted		140	
Finished light weight		2088	
Actual Salt Water Deadweight		2223	
Load Draft Bottom of Keel		24'-8"	
Lloyd's Summer Deadweight		21'-9"	
Load Displacement on		18179	

Survey fee - - - - - \$400.00


Referred to the Chief Ship Surveyor.

*John J. Gardner*

Referred to Mr. Mayne

31 JUL 1922

0185



© 2021

Lloyd's Register  
Foundation

This  
"While  
not neither  
certificate is  
of judgment

rt. B. 1. - 4