

M.V. "WELLFIELD".  
-----

Rule Dimensions:- 385' x 51.25' x 30.5'  
-----

This vessel, which is a longitudinally framed tanker, was built by Messrs. The Tyne Iron Shipbuilding Co. in 1924.

A letter has been received from Messrs. Curchin & Watson stating that the Owners propose to increase the length by 24 feet 3 inches, and they desire to be informed what extra scantlings, if any, will be required.

The case has been examined, and it is found that the scantlings as already provided in the ship are in accordance with the Committee's Rules for a vessel of the increased length now proposed.

The suggested alteration will, however, increase the equipment numeral by 1 grade, and it will be necessary to replace the present third bower anchor by an anchor weighing 63 cwts., and to place on board an additional 15 <sup>as</sup> fathoms of cable of the same size/at present on board.

The case has been discussed in this Office with Mr. Curchin, to whom the foregoing alterations have been indicated, and it is submitted Messrs. Curchin & Watson be informed accordingly.

*Ltr: 24.7.31  
Ans: 28<sup>th</sup>  
O.C. two plans have*

27.7.31

Lloyd's Register  
Foundation

W134-0122