

COPY

Lloyd's Register of Shipping.

9, OURA (KAIGAN-DORI)

NAGASAKI.

25th October 1934.

CERTIFICATE No.1073-B.

This is to Certify that at the

request of Messrs. Mitsubishi Denki Kaisha, Ltd., Nagasaki, attend at their works, on the 21st & 22nd September 1934, in order to examine under test, Two compound wound, direct current, 80 K.W. Generators, No.15382 & 15383, of 110 volts, by 727 amps at 1500 revolutions per minute.

These Generators ordered by Messrs. Mitsubishi Jukogyo Kaisha, Ltd., Nagasaki, are intended for their Vessel No.594.

The Generators were submitted to the following tests:-

Full load test of 5 hours duration.
25% overload test of 2 hours duration.
50% overload test for 1 minute.
Over speed test (1800 r.p.m.) for 1 minute.

The rise of temperature was measured by thermometers & on completion of trials, high voltage (2000 volts, A.C.) and insulation tests were carried out, and all found satisfactory.

For purposes of identification the Generators have been stamped as follows:-

Gen.No.15382.

L L O Y D'S

No.1073-B. R

T.K. 21-9-34.

Gen.No.15383.

L L O Y D'S

No.1073-C. R

T.K. 22-9-34

T. Kurishima


ASSIST.SURVEYOR TO LLOYD'S REGISTER.

Fee Yen 60:00

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society.

34. C.



Lloyd's Register
Foundation