

Lloyd's Register of Shipping.
SURVEYS FOR FREEBOARD.—STEAM SHIPS.

ARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH
OP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR
ITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS
CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey
Date of Survey 23/4/30
Name of Surveyor

Ship's Name. Haring
Port of Registry and Nationality.
Official Number.
Gross Tonnage.
Date of Build.
Particulars of Classification. 10001 Carrying petroleum in bulk.

Number in Register Book
LENGTH. 490'-0"
BREADTH. 65'-0"
DEPTH. 37'-0"
UNDER DECK TONNAGE.
Frame Depth
Ceiling
Peak
Tanks

Co-efficient of fineness.....
Any modification necessary {
[Para. 4 (a) to (e)]* }
Co-efficient as corrected assumed 28.76

Sheer { Stem..... 98" }
at { Sternpost ... 48" }
Sheer at 1/2 of the length from { Stem }
Sternpost }
Gradual mean Sheer 36.63 ✓
Standard mean Sheer [Table, Para. 18] 59.00 Correction
Difference..... 22.37 ÷ 4 = 5.59 ✓
If limited as Para. 18 (f) + 5 1/2

Rise in Sheer { At front of bridge house..... }
from amidships { }
[Para. 18 (e)] { At after end of forecastle }
Fall in Sheer { }
Para. 18 (d) }
Length uncovered Correction

ALLOWANCE FOR DECK ERECTIONS:—
Freeboard, Table C..... 10'-3 1/4" - 3'-2" = 7'-1 1/4"
Correction for Length, if required (Para. 12, 13, and 14) + 4"
Freeboard by Table A, corrected for sheer, and for length, }
if required (Para. 11, 12, 13, and 14) }
Difference 4'-0"
Percentage as below..... 24.75%
11.88

Correction for R. Q. Dk. if engine and boiler openings not }
covered by bridge house (Para. 11) }
Allowance for Deck Erections 12"

	Length.	Length allowed.	Height.
Forecastle.....	32	32.00	
Bridge House	36	36.00	
† Raised Qr. Dk.....			
Poop.....	126	126.00	
Total		194	= 396
Length of Ship		490	
Corresponding percentage { (Para. 11, 12, 13, or 14) }			24.75%

FREEBOARD recommended amidships from centre of Disc to top of Statutory Deck Line, Wood (Steel) Deck:—
Fresh Water Line above centre of Disc
Indian Summer Line " " "
Winter Line below " "
Winter North Atlantic Line " " "

† If the frames, skin planking, or ceiling are of unusual thickness the breadth of vessel to inside of ceiling should be reported if possible.
† In vessels obtaining an allowance for deck erections under Para. 11 where the sheer drops abaft amidships the height of the R.Q.D. is to be taken from the level of the top of the amidship beam.
§ In flush-decked vessels the total standard mean sheer means the sheer measured at the stem and stern-post. In vessels having poops and forecastles, it means the sheer measured at points distant one-eighth of the vessel's length from stem and stern-post.

Moulded Depth as measured..... 37'-0"
Rule wood Deck etc. - 3 1/4"
Addition for Keel below base line 36'-8 3/4" ✓
for draught record..... inches.

CORRECTION FOR LENGTH.
Length of Ship on Loadline..... 490
Length in Table 440.75
Difference 49.25
Correction for 10ft., Table A. 17 Table C. 8
× Difference divided by 10 8.37 (if required.) 3.94 ✓
If 1/10ths length covered divide by 2 + 8 1/2 ✓ + 4 ✓

CORRECTION FOR IRON DECK.
Proportion covered, if less than 1/10ths length covered
Thickness of usual wood deck, less stringer Allowed in M.C. Deck

CORRECTION FOR ROUND OF BEAM.
Breadth at Gunwale amidships.....
Round of Beam Assumed normal
Normal round.....
Difference ÷ 2 =
Proportion of Deck uncovered (Para. 19)

Freeboard, Table A	123.14	10'-3 1/4"
Correction for Sheer	+ 5.59	+ 5 1/2"
	128.73	10'-8 3/4"
Correction for Length	+ 8.37	+ 8 1/2"
	137.10	11'-5 1/4"
Allowance for Deck Erections	- 11.88	- 1'-0"
	125.22	10'-5 1/4"
Correction for Round of Beam.....		✓
Correction for fall in Sheer (if any).....		✓
Correction for Steel Deck (if required)		✓
Additions for non-compliance with provisions of } Para. 11 (d) and (e) ‡ }		✓
Other Corrections (if any)		

Winter Freeboard 10'-5 1/4" ✓
Summer Freeboard (62.72) 7' 9'-10 1/4" ✓
Indian Summer Freeboard
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured }
in accordance with the Statute is not taken at the }
intersection of the wood or steel deck with side.

Winter Freeboard from deck line
Summer " " " "
Indian Summer " " " "
N. A. Winter " " " "

37'-0 3/4"
9'-10 1/4"
27'-2 1/2"
© 2021

† State dimensions of freeing port area on back of this form.
† The Surveyor should state whether the fall in sheer as reported is measured relatively to the straight line of keel or to the water line. If measured relatively to water line the vessel's draft at time of survey, and also the usual load draft forward and aft should be reported.

Forecastle?

Lloyd's Register
Foundation