



Lloyd's Register of Shipping,

3, Steinhoeft,

Hamburg, 3rd August 1937.

LLOYD'S REGISTER
Received
6/8
LONDON

Reference

Dear Sir,

320 ll.

The s.s. "ZEMBRA" has been purchased by Messrs. Krupp's (Fried.) Reederij en Transportbedrijf N.V., Rotterdam, and has been renamed "OSLEBSHAUSEN". The Official of the German Boiler Authorities went on board on the 27th ult. and when the starboard main boiler was hydraulically tested in accordance with the requirements of the German Boiler Regulations the shell plate and both end plates cracked at a pressure of 22.5 kgs/cm² with the result that the whole boiler is no longer fit for use. In consequence of what has happened with the starboard main boiler the hydraulic test of the port main boiler has for the meantime been postponed until the results of the investigation which is now being made in connection with the starboard boiler are obtainable. I may add that according to the latest requirements of the German Boiler Regulations the boiler pressure is to be determined by 1.5 times of the working pressure of the boiler plus 3.5, so that in the case of this boiler the hydraulic pressure amounted to $1.5 \times 14.5 + 3.5 = 25.25$ kgs/cm². *(Boiler made for testing near Berlin)*

The Owners have made arrangements to obtain a new boiler in Holland or elsewhere and I am advising you of the facts, as far as they are available at the present moment, in order that you may be informed when requests for the acceptance of boilers for this vessel are being submitted to the Committee in the near future.

Lloyd's Register
Foundation

W1356-0175 1/2

As soon as the results of the investigation made into the failure of the starboard boiler are available here they will be passed on for your information.

I am, Dear Sir,

Yours faithfully,

for A. Chisholm:



The Secretary,
London.



© 2021

Lloyd's Register
Foundation

0175 2/2

Referred to the Chief Engineer Surveyor

Also for Mr. Hill to note.
- 5 AUG 1937

M/B


W.C.
H.C.

CIRCULAR

NEW ORALERS

9/8

The Secretary,
London.



For A. Chapman:

Yours faithfully,

I am, Dear Sir,

they will be based on the work information.
The nature of the proposed policy are available here
as soon as the results of the investigation have info



© 2021

Lloyd's Register
Foundation