

NEWCASTLE-ON-TYNE

C.6293.

Index No.

24489

Rpt. C. 11 (Contd.)

Lloyd's Register of Shipping. NOV 24 1937

Ship's Name *STANBRIDGE*Official No. *139200*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

Additional latches to No 5 main Tank 1 Port and 1 starboard
3'-8" x 3'-0" coamings 36" x 40. Slunged w. I. bar secured
with toggles.

Forecastle Deck Ventilator 1-6" dia. 15" boaming to Fore peak store.

1-12" " 37" " " Store

4-12" " 37" " " Accommodation

4-6" " 13" " " "

Poop Deck Ventilator 4-15" dia. 18" boaming to after peak store

1-19" " 25" " " Staring gear

12-6" " 13" " " Accommodation.

Forecastle Deck Air pipes. 2-4" dia. 15" to lip to Fore peak tank.


2-4" " 15" " " Fore deep tank

2-3½" " 16" " " " "

1-4" " 18" " " Fore peak Tank.

2 Skylights on Forecastle deck to Accommodation.

4'-2" x 4'-0" x 13" coamings. Strongly constructed
of steel with 2 hinged steel flaps each secured
with 4 toggles.



© 2020

Lloyd's Register
Foundation

W1360-0022