

REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

18 MAR 1935

16 MAR 1935

Received at London Office

Date of writing Report 19 When handed in at Local Office 19 Port of HULL

No. in Survey held at Hull Date, First Survey 28th Feb. 1935 Last Survey 13th March, 1935
 Reg. Book. (Number of Visits.....3.....)

on the Steel S.S. "Kingston Beylonte" Tons { Gross 447.95
 Net 173.87

Built at Beverley By whom built boots Welton & Gemmell^{td} Yard No. ✓ When built 1935

Owners Kingston Steam Trawling Co.^{td} Port belonging to Hull.

Electric Light Installation fitted by W. Broady & Son. Contract No. ✓ When fitted 1935

Is the Vessel fitted for carrying Petroleum in bulk no.

System of Distribution Two Wire

Pressure of supply for Lighting 100 volts, Heating 100 volts, Power ✓ volts.

Direct or Alternating Current, Lighting Direct Power ✓

If alternating current system, state frequency of periods per second ✓

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes

Generators, do they comply with the requirements regarding rating Yes, are they compound wound Yes

are they over compounded 5 per cent. Yes, if not compound wound state distance between each generator ✓

Where more than one generator is fitted are they arranged to run in parallel ✓, is an adjustable regulating resistance fitted in series with each shunt field ✓

Are all terminals accessible, clearly marked, and furnished with sockets Yes, are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes Are the lubricating arrangements of the generators as per Rule Yes

Position of Generators Starboard side of engine room.

is the ventilation in way of the generators satisfactory Yes, are they clear of all inflammable material Yes

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators ✓ and ✓, are the generators protected from mechanical injury and damage from water, steam or oil Yes

are their axes of rotation fore and aft Yes

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes are the prime movers and their respective generators in metallic contact Yes

Main Switch Boards, where placed Beside generator

If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes

are they protected from mechanical injury and damage from water, steam or oil Yes, if situated near unprotected

woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards ✓ and ✓

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes, is all insulation of high dielectric strength and of

permanently high insulation resistance Yes, if semi-insulating material is used, are all conducting parts insulated from the slab

with mica or micaite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework ✓

and is the frame effectively earthed Yes Are the fittings as per Rule regarding: — spacing or shielding of live parts

Yes, accessibility of all parts Yes, absence of fuses on back of board Yes, proportion of omnibus

bars Yes, individual fuses to voltmeter, pilot or earth lamp Yes, connections of switches Yes

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches D.P. linked

Switch for generator Outgoing circuits controlled by S.P.


switches and protected by fuses on each pole

Instruments on main switchboard One ammeters One voltmeters ✓ synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system Earth lamps.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes



Cables: Single, twin, concentric, or multicore Twin are the cables insulated and protected as per Tables IV or V of the Rules Yes

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load 1 Volt

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets Yes

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound None

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage Yes

Support and Protection of Cables, state how the cables are supported and protected Armoured cables G.I. clips
Lead covered in cabin spaces with brass clips.
 If cables are run in wood casings, are the casings and caps secured by screws , are the cap screws of brass , are the cables run in separate grooves . If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII Yes

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements None

Joints in Cables, state if any, and how made, insulated, and protected None

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands Yes

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed Yes state the material of which the bushes are made Lead

Earthing Connections, state what earthing connections are fitted and their respective sectional areas

are their connections made as per Rule

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule Yes

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven None

Navigation Lamps, are these separately wired Yes, controlled by separate switch and separate fuses Yes, are the fuses double pole Yes
 are the switches and fuses grouped in a position accessible only to the officers on watch Yes
 has each navigation lamp an automatic indicator as per Rule None

Secondary Batteries, are they constructed and fitted as per Rule None

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight Yes
 are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected None
 are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected None
 how are the cables led None

where are the controlling switches situated

Searchlight Lamps, No. of , whether fixed or portable , are their fittings as per Rule

Arc Lamps, other than searchlight lamps, No. of , are their live parts insulated from the frame or case , are their fittings as per Rule

Motors, are their working parts readily accessible , are the coils self-contained and readily removable for replacement
 are the brushes, brush holders, terminals and lubricating arrangements as per Rule , are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material
 are they protected from mechanical injury and damage from water, steam or oil are their axes of rotation fore and aft
 if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type
 if not of this type, state distance of the combustible material horizontally or vertically above the motors and

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings
 If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office

PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.	
		Kilowatts.	Volts.	Amperes.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN	One	8	100	80	350	Steam Engine		
AUXILIARY								
EMERGENCY								
ROTARY TRANSFORMER								

GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR	1	0.060	19	0.064	68	83	40	V.P.R.	
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER MOTOR GENERATOR									
ENGINE ROOM	1	0.00299	3	0.036	6	12	40	"	L.C. + armoured
BOILER ROOM	1	0.00299	3	0.036	2	12	60	"	"
AUXILIARY SWITCHBOARDS									
ACCOMMODATION Mr. ship	1	0.01046	7	0.044	10.5	31	150	"	"
" Forward	1	0.00701	7	0.036	8	24	250	"	"
" aft	1	0.00701	7	0.036	7	24	30	"	"
Navigation mains	1	0.00701	7	0.036	5	24	150	"	"
WIRELESS	1	0.00701	7	0.036	10	24	150	"	"
SEARCHLIGHT									
MASTHEAD LIGHT	1	0.00299	3	0.036	1	12	180	"	"
SIDE LIGHTS	1	0.00299	3	0.036	1.5	12	24	"	L.C.
COMPASS LIGHTS	1	0.00194	3	0.029	1	7.8	20	"	L.C.
POOP LIGHTS	1	0.00194	3	0.029	1	7.8	130	"	L.C. + armoured
CARGO LIGHTS	1	0.00194	3	0.029	6	7.8	20	"	"
ARC LAMPS									
HEATERS	1	0.00299	7	0.036	10.	12	30	"	L.C.

MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS										
AIR COMPRESSOR										
FRESH WATER PUMP										
ENGINE TURNING GEAR										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS										

All Conductors are of annealed copper conforming to British Standard Specification No. 7.
 The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.
 The foregoing is a correct description.

WM BROADY & SON
 ENGINEERS
 57, BRISTOL STREET
 HULL.

Electrical Engineers.

Date 5th March 1935.

COMPASSES.

Distance between electric generators or motors and standard compass 75 ft

Distance between electric generators or motors and steering compass

The nearest cables to the compasses are as follows:—

A cable carrying 0.5 Amperes to feet from standard compass - feet from steering compass.

A cable carrying 0.5 Amperes to feet from standard compass - feet from steering compass.

A cable carrying - Amperes - feet from standard compass - feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes

The maximum deviation due to electric currents was found to be no degrees on any course in the case of the standard compass, and no degrees on any course in the case of the steering compass.

COOK, WELTON & GEMMELL, LTD.

Secretary & Director,

Builder's Signature.

Date 14th Mar 1935

Is this installation a duplicate of a previous case Yes If so, state name of vessel Kingston & Lysolite

General Remarks (State quality of workmanship, opinions as to class, etc.) This electrical installation has been fitted on board under special survey and in accordance with the rules. It has been tried under working conditions, found satisfactory and is eligible in my opinion, to have the notation of "Electric Light."

Noted
 F. J.
 18/3/35

Total Capacity of Generators 8 Kilowatts.

The amount of Fee ... £ 4 : 0 :

When applied for
 16 MAR 1935

Travelling Expenses (if any) £ :

When received
 3.4 35

C. Knoffatt
 Surveyor to Lloyd's Register of Shipping.

Committee's Minute

TUE. 19 MAR 1935

Assigned

See Bul. F.E. 45580



© 2020

Lloyd's Register Foundation

Im. 9.30.—Transfer.
 (The Surveys are requested not to write on or back in the space for Committee's Minute.)