

Messrs. Bartram & Sons' Yard No. 281.

Plan showing proposal to convert coal pockets on fore side of boiler room into oil bunkers submitted, in duplicate, by the Sunderland Surveyors.

It is submitted the Surveyors be informed that the scantlings and arrangements as shewn and amended will be approved, provided they be carried out to their satisfaction.

The requirements of the Rules for the application of electric arc welding to ship construction should be complied with.

The requirements of Section 20B, paragraph 9, will also require to be complied with, and if coal is to be carried in the side bunkers at the same time as oil fuel is carried in the bunkers, efficient steel lining will require to be fitted at the forward end of the coal bunker.

The Surveyors should satisfy themselves that the riveting of the existing coal bunkers is in all respects suitable for oil tight work.

a sketch showing the oil fuel suction & filling pipes, and the arrangement of air sounding pipes in connection with the new bunkers should be submitted

28. 4. 38.

CR

[Signature]

J. Robt

*P. 14. 4. 38
Ord. 29. 4. 38
plans retained.*

[Signature]



© 2019

Lloyd's Register

Foundation

W143 + 0026