

[illegible]

Correspondence.—State dates and initials of letters respecting this case (Reference should be made to any correspondence connected with this case)
m 10/07, 24/9/07, 5/10/07, 11/10/07, 21/11/08. E 18/12/07

Workmanship. Are the butts of plating planed or otherwise fitted? Planed & fitted.
Is the riveted work properly closed? Yes
Are the liners between the frames and plates solid single pieces? Yes + forged from
Do the holes for riveting plate to frames, butt straps, or plate to plate, &c., conform well to each other? Yes
Are the rivet holes well and sufficiently countersunk in the plate and punched from the faying surfaces? Yes
Do any rivets break into or through the seams or butts of plating? A few only.
Are the butts of Plating, Stringers, &c., properly shifted and strapped? Yes
Have all the upper and weather decks been tested as required by the Rules (Sec. 23, par. 24)? Yes State results of tests Satisfactory.
Have all the gutterways been tested as required by the Rules (Sec. 23, par. 25)? Yes State results of tests Satisfactory.

General Remarks (State quality of workmanship, &c.) The workmanship throughout is good.
The vessel has been built in accordance with the approved plans of the Secretary, London referred to & in general conformity with the Rules for the class contemplated. The vessel is constructed to carry oil in bulk & is divided into 16 oil tanks & 4 summer tanks, the cargo tanks have been lined with a lead of water 15 ft above main deck (see Sec. 4 cl. 25/1/08) An installation of electric light is fitted.
This vessel is somewhat similar to F.S. Service No. 628.

10 Plans & 3 forging reports enclosed.
The Surveyor should state the Number of Report and Name of any Sister Vessel.

PARTICULARS FOR RECORD in the REGISTER BOOK.—Length of Poop 28 ft., R.Q.D. or Break — ft., Bridge Dk. 83 ft., Forecastle 38 ft. ft. (in feet and tenths). When the Poop is joined to the B.D., this should be distinctly stated

No. and Material of Decks (if Iron or Steel) and whether wholly or partially covered with wood, and No. of tiers of Beams (this information is to be given as it should appear in the Register Book) 2 Dks (1st d. up to bow post steel) & web frames
Official No. ; Signal Letters
How are the surfaces preserved from oxidation? Inside No paint or cement in oil tank outside Paint.

PARTICULARS OF WATER BALLAST.—State whether the Double bottom is constructed on the cellular system or with girders on floors Cell in 8th space.

Where fitted.	*Length. Feet.	Water Capacity. Tons.	Where fitted.	*Length. Feet.	Water Capacity. Tons.
Double bottom, aft,	—	—	Fore peak tank,	—	194
Double bottom, under Engines and Boilers,	54.2	198	After peak tank,	—	36
Double bottom, if under Engines only,	—	—	Midship deep tank,	—	—
Double bottom, if under Boilers only,	—	—	Other tanks, if fitted,	—	—
Double bottom, forward,	—	—	(If necessary, furnish further information by sketch.)	—	—

* The wells are not to be included in the lengths of the tanks. State whether the above have been tested as required by the Rules Yes

Order for Special Survey No. 4712
Date 5-7-04
No. 629 in builder's yard.
DATES of Surveys held while building
1904: Sept 5, 11, 17, 20, 26 Oct. 1, 3, 8, 10, 11, 14, 16, 24, 29 Nov. 1, 5, 7, 11, 13, 15, 18, 19, 21, 25, 26, 29 Dec. 5, 10, 13, 17, 18, 19, 23 Jan. 10, 15, 18, 20, 22, 24, 26, 29 Feb. 4, 10, 12, 17, 19, 20 Mar. 4, 11, 12, 17, 25 Apr. 2, 3, 7, 9, 13, 14, 16, 24, 29 May: 1, 5, 7, 12, 14, 18, 21, 24, 27, 29, 30 June 2, 3, 5, 11, 16, 18, 19, 23, 26, 29 July 1, 3, 6, 7, 8, 13, 15, 17, 22, 24 Aug. 5, 6, 7, 13
Total No. of Visits 96.

The amount of Entry Fee.....£ 5 : : :
Special Survey Fee ...£140 : 12 : 6
Travelling Expenses, if any £ : : :
Fees applied for,
13. 8 1808
Received by me,
18. 8 1808
Certificate to be sent to Sunderland.
State whether the Vessel has been built under Special Survey Yes
I am of opinion this Vessel should be Classed 100 ft carrying petroleum in bulk.
With, or without Freeboard, as condition of Class Without.
Surveyor to Lloyd's Register of British and Foreign Shipping. F.R. Norton.

Committee's Minute
Character assigned
100 ft
carrying petroleum in bulk
Lloyd's at 8.08
Inquire
Fri. 21 AUG 1908
Costs incurred 2/108
W 1147-0162 2/12