

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
Signal Letters (if any) L.D.R.J.

Official Number.	Name of Ship.	No., Date, and Port of Registry.		
161,284.	Bahadur.	139 in 1929 London.		
No., Date, and Port of Previous Registry (if any). -----				
Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship Single Screw.	Port Glasgow.	1929	Lithgows Limited Port Glasgow.
Number of Decks ...	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	405	Tenths. 0
Number of Masts ...	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	403	8.4
Rigged ...	Schooner	Main breadth to outside of plank ...	54	0
Stern ...	Elliptical	Depth in hold from tonnage deck to ceiling at midships ...	28	8
Build ...	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	--	--
Galleries ...	None	Depth from top of beam amidships to top of keel ...	32	3.7
Head ...	None	Depth from top of deck at side amidships to bottom of keel ...	31	3.4
Framework and description of vessel ...	Steel Cargo	Round of beam ...	1	1
Number of Bulkheads ...	Six	Length of engine room, if any ...	51	4
Number of water ballast tanks, and their capacity ...	Seven in D.B. - 1186 tons Art. Peak - 31 tons Fore Peak - 118 tons Deep Tank - 981 tons	PARTICULARS OF DISPLACEMENT.		
Total to quarter the depth from weather deck at side amidships to bottom of keel ...		Tons. 11089 Ditto per inch immersion at same depth ... 42.50 Tons.		

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B.H.P. I. H. P. Speed of Ship.
One	Direct Acting Vertical Triple Expansion	Engines. British	Engines. 1929	Engines. David Rowan & Co., Ltd.,	Three 24½"	48"	-----	446 ----- 2650
No. of Shafts.	Particulars of Boilers.							
One	Horizontal Return Tube Single End Number Two Main one Donkey Iron or Steel Steel (ex tubes) Loaded Pressure 210 lbs. 110 lbs.	Boilers. British	Boilers. 1929	Boilers. Glasgow.	42" 70"			12 knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	5023.65	On account of space required for propelling power	1735.56
Space or spaces between Decks ...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	202.01
Turret or Trunk ...		These spaces are the following, viz. (Number of Seamen or Apprentices for whom accommodation is certified.....)	
Forecastle (Side House in) ...	32.25	Houses in Forecastle, Bridge & Poop and above Bridge Deck.	
Bridge space (Houses in) ...	56.55		
Poop or Break ...	87.74		
Side Houses ...	59.14		
Deck Houses ...	75.76		
Chart House ...	4.26		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	64.49	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ...	19.77	Master's Accommodation 15.46) Chart Space 4.26) Wireless Telegraphy Space 3.74) Boatswain's Store 20.05) Water Ballast Spaces 45.34)	83.85
Gross Tonnage ...	5423.61	Cubic Metres 15348.82	
Deductions, as per Contra ...	2026.42	5734.77	
Register Tonnage ...	3397.19	9614.05	Total ... 2026.42

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 640.63 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 160.49 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open space in Forecastle	40.5 feet in length	-	40.61 tons
" " " Bridge (Part 1)	58.2 " " "	-	196.47 "
" " " " (Part 2)	41.8 " " "	-	50.04 "
" " " " (Part 3)	41.8 " " "	-	50.04 "
" " " " (Part 4)	20.5 " " "	-	53.37 "

Name of Master

Certificate of { Service No.
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

The Asiatic Steam Navigation Company, Limited
45, St. Mary Axe,
London.

Shares. Sixty-four.

Dated 16th August, 1929.

Alfred Geoffrey Turner of
same address—Manager—