

James Pollock Sons & Co. Ltd

TELEGRAMS: SPECIFIC, LONDON.

TELEPHONE: NO 493 CENTRAL (3 LINES)

CODES USED

A.I.,
A.B.C. 4TH & 5TH EDITION.
ENGINEERING.
WESTERN UNION.
OUR PRIVATE CODES.

LOYDS REGISTER
JGF/J.
22 JUN 1914

23

*3 Lloyds Avenue,
London, E.C.*

20th June, 1914.

BOLINDER'S CRUDE OIL ENGINES.

Lloyds Registry of Shipping,
Fenchurch Street,
London, E.C.

Dear Sirs,

"Lewes Castle".

Further to yours of the 16th ult. We are
in receipt of a reply from our Principals in Stockholm,
and the following is an extract from same -

"The air receivers furnished with your motors
are acetylene gas welded at joints, annealed
and tested to a hydraulic pressure of 25
atmospheres. The certificate of test is
marked with the same number as that found on the
receiver.

With regard to material, we use first
class Siemens Martin boiler plate, having an
ultimate tensile strength of not less than 36
Kg. per square m.m. and an elongation of not
less than 25%. We enclose sketch of these
receivers".

We trust the particulars given are as
required .

Yours faithfully,

For JAMES POLLOCK SONS & CO. LTD.

J. J. Freeman



© 2021

Lloyd's Register
Foundation

W1503-0036

