

COPY.

# Lloyd's Register of Shipping,

71, Fenchurch Street, E.C.3.  
18th August, 1939.

REF. S. 585.

ENCLOSURE.

Dear Sirs,

With reference to your letter of the 11th instant forwarding three plans, of sanitary, air and sounding pipes proposed to be fitted in the motor ship "BEN HANN", I beg to acquaint you that provided the arrangement be carried out as shewn and amended thereon and to the satisfaction of the Society's Surveyors and also provided the remaining requirements of Section 34 of the Society's Rules (1938-39) be complied with so far as they are applicable, the same will be approved.

One copy of the plan is returned herewith, and I may say that as the waterclosets proposed do not incorporate flap valves with metal seatings, the storm valves at the outer ends of the discharges should be provided with positive means of closing from positions above the upper deck and with indicators shewing whether the valves are open or closed; alternatively, two separate automatic non-return valves should be provided for each discharge, the upper valve in each case being situated so that it may be readily accessible for examination under service conditions.

I am, Dear Sirs,  
Yours faithfully,

The Rowhedge Ironworks Co.Ld.,  
ROWHEDGE,  
nr. Colchester.

Assistant Secretary.

Lloyd's Register  
Foundation

W151-0148