

C O P Y

THE ROWHEDGE IRONWORKS COMPANY LIMITED

ROWHEDGE NEAR COLCHESTER.

Order No.40796.

Ref. M.585.

21st March 1939.

Messrs Norris, Henty & Gardners Ltd.,
Barton Hall Engine Works,
Patricroft Lanes.

Please supply:-

Auxiliary machinery for 305 Ton Tanker for
National Benzole Co.Ltd.

One 3L2 engine for driving Cargo pump. Engine to develop 30 B.H.P. @ 1000 r.p.m. To be mounted on baseplate extended to carry a Hyland hydraulic pump at one end and a worm reduction gear at the other end. These two units to be supplied by us for you to fit. Engine to be fitted with Gardner clutch, outer bearing and flexible coupling to take reducing gear. Other end of crankshaft to be fitted with drive for Hyland pump.

One Auxiliary set comprising 1L2 engine developing $9\frac{1}{2}$ B.H.P. at 1000 r.p.m. mounted on combination baseplate and driving one 5 k.w. 110 volt compound wound generator, flameproof, with shunt regulator, One Dawson & Downie vertical D.A. pump two throw $4\frac{1}{2}$ " x 5". One Gardner T.S.1 air compressor.

One set of spare brushes and springs for generator.
All to be in accordance with our inquiry of 17.2.39.

To be constructed to Lloyds requirements and their

Lloyd's Register
Foundation
W151-0185(112)

certificate supplied.

Drawings showing general arrangement of these sets to be submitted to us in triplicate for approval before the work is put in hand.

The whole to be to the satisfaction of our Clients and of ourselves.

A complete set of cloth tracings and 4 white prints off each to be supplied for each auxiliary.



© 2019

Lloyd's Register
Foundation

W151-0185(212)