

C O P Y

THE ROWHEDGE IRONWORKS COMPANY LIMITED

ROWHEDGE NEAR COLCHESTER.

Order No. 40793.

Ref.M.585. 305 Ton Tanker for N.B.Co. 21st March 1939.

Messrs Worthington Simpson Ltd.,
Newark on Trent.

Please supply:-

One 9½" x 10" horizontal Duplex pump with gunmetal fitted pump end and stainless steel pump rods. To have a capacity of 100 tons/hour spirit at 49.25 cub. ft. per ton against a pressure of 50 lbs. per sq. inch. running at a crankshaft speed of 55 r.p.m. Pump to be of enclosed type with single reduction gear and bare shaft extension. To be complete with delivery air vessel, gauge cocks on suction and delivery branches, special spanners etc. A 5" relief valve to take full output of pump to be supplied for fitting in our pipe line. All in accordance with your Drawing No.1937/4133/2.

One 10" x 10¼" x 12" horizontal duplex steam pump to be capable of the same output as above when working with steam at 100/200 lbs. per sq. inch and at 38 double strokes per minute.

Pump end to be fitted similarly as for power pump.

To be generally as per your drawing No.FF.1000/1.

One set of spare gear for power pump mounted on rack.

One ditto for steam pump.

All to be of British material and workmanship throughout and to be guaranteed against any defect discoverable within 6 months of the time of vessels delivery to owners.

© 2019

Lloyd's Register
Foundation

(211/2810-15/11)

To be completed to the satisfaction of the Consulting Engineers appointed by the Owners and detail drawings to be submitted to us in triplicate for their approval before the work is put in hand. One set of cloth tracings and 4 white prints off each for each pump to be supplied on completion.



© 2019

Lloyd's Register
Foundation

W151-0186(2/2)