

COPY.

THE ROWHEDGE IRONWORKS COMPANY LIMITED

ROWHEDGE, NR COLCHESTER.

26th June, 1939.

Order No. 41413.

S.585. 305 ton motor tanker.

The Newport & South Wales Tube Co. Ltd.,

41 Easy Row,

Birmingham 1.

Please supply,

One weldless steel tubular mast and derrick, in hot finish made from steel having a tensile strength of 35 tons minimum per square inch.

Mast 32 ft. long overall, comprising.

12.1/2"	o/d.	x	3/8"	thick	x	20'0"	} stepped.
10.1/2"	"	x	"	"	x	9'0"	
9.1/2"	"	x	"	"	x	3'0"	

Derrick 22'6" long overall. 6.1/2" o/d. at centre, stepped to 4.1/2" o/d. at ends x 1/4" thick throughout.

To Lloyd's survey, requirements and tests at your Works before despatch. Certificate supplied.



© 2019

Lloyd's Register
Foundation

W151-0236