

s.s. Nos. 350 & 355.

SPECIFICATION OF ANCHORS & CHAINS.

Bower Anchors each 100 cwt. ✓

" " 85 cwt. ✓

Stream " 22 cwt. ✓

Kedge " 9 cwt. ✓

Rule


36 1/4

18 3/4

55

"Hall's" Patent

Stockless.

130 Fms., 2 1/4" Stud Link Chain Cable, shackled complete (i.e.,
including 2 end shackles to each cable" Minimum weight = 1247 cwt.,
of "Netherton  Special Best Best" quality.

Government Pattern Mooring Swivel. }

To be tested

End Shackles and 6 Anchor Keys. }

as Anchors & Chains.

Joining Shackle.

Buoy Shackle to P. & O. Coys., Special design.

Joining Shackles for Locker.

Admiralty Sliphooks, to be in excess of strength of Chain Cable.

SPECIFICATION OF HAWSERS.

1 - 7" Steel Wire Hawser, 130 fms. long. In lieu of Stream Chain.

1 - 6" " " " 120 " "

2 - 4 1/2" " " " 120 " "

2 - 3 1/2" " " " 120 " "

2 - 9" Manilla Hawsers 120 Fms., long.

2 - 8" " " 120 " "



© 2021

Lloyd's Register
Foundation

W1523-0085