

h Jordan

Steel Screw Steam Trawlers Nos. 424 & 425 proposed to be built by Messrs. Cochrane & Sons with a view to class 100A1, "Steam Trawler".

Rule Dimensions ; 153.5 × 25 × 14.5

Equipment Number; 7690.

The equipment Number of this vessel is 390 over the highest grade provided for in Table 22 of the Rules, and the equipment determined by an extension of the table and that proposed by the Builders are as follows, viz:-

Equipment as per extension of Table 22 for Steam Trawlers.

Equipment as proposed by the Builders.

1 bower anchor 7 cwts ex stock	1 bower anchor 7 cwts. ex stock
1 " " 6½ " "	1 " " 6½ " "
1 " " 3½ " "	1 " " 3½ " "
120 fms. 1 3/16" chain cable	120 fms. 1 3/16" chain cable
60 " 7" hawser	60 " 7" hawser
60 " 5" warp	60 " 5" warp

It will be observed that the equipment as proposed by the Builders is in agreement with that required by an extension of the Table 22 for Steam Trawlers, and it is submitted for the favourable consideration of the Committee for the figure 1.

C.B.
22. 10. 07.

TUES. 22 OCT 1907

Approved
M.

Approved



© 2021 Lloyd's Register Foundation

full
22-10-07

W1534-0096