

Shipbuilders: Messrs. BURNTISLAND S.B. CO. LTD. Yard No. 238.

Engineers: Messrs. D. ROWAN & CO. LTD. Engine No. 1048.

It is submitted that the ~~Master~~ Glasgow Surveyors be informed that the Firm's remarks regarding the ~~recent~~ appears ~~was~~ plans of piping arrangements have been noted.

With regard to the arrangement of auxiliary steam pipes, it should be pointed out that superheated steam can be supplied to the auxiliary steam range through pipes N° 113, 114, 119 + 119A.

In view of the number of different sources of supply of superheated steam to the auxiliary range, it is still considered it would be difficult to obtain an effective temperature control in the auxiliary range.

In the circumstances it is recommended that the steam pipes to the port side auxiliaries should be made of Steel. Their fittings should also be made of steel or other approved material.

If, however, the pipes are already made, they could be accepted if the precautions suggested by the Firm are carried out to the Surveyor's satisfaction, but, as an additional precaution, they should include in the instructions on the warming plate, a regulation to the effect that valves M. 124 must be kept shut when not using these for steam to the main engines.

The Firm's remarks regarding the Ballast + Oil Fuel Piffs have also been noted & are in order.

Return

plan.

Retain

copy.

1m, 11.38. T.

J.H.B.

COR
26/1/40.

Royal's Register
Foundation

W154-0200