

PUMPING ARRANGEMENT Endorsement.

Shipbuilders: Messrs. *BURNTISLANDS B. Co. LTD*

Yard No. *238*.

Engineers: Messrs. *D. ROWAN & Co. LTD*

Engine No. *1048*

Owners: Messrs.

It is submitted that the plans of *PIPING*

~~Arrangements~~ *Arrangements* **IN THE MACHINERY SPACE**

merit approval, provided the arrangements be as

shown and amended on the plans *S<sub>A</sub>* and the remaining

requirements of Sections 20 and 34 of the Rules (19*39*-40)

be complied with so far as they are applicable.

\* { the steam & feed pipes be made under the usual conditions  
of survey & testing,

It is noted that the plans indicate one centre suction to the after end of N<sup>o</sup> 4 d. b. tank, which is divided on the centre line, but it is concluded that arrangements will be made in the tunnel for port & starboard sections.

The Surveyors should be informed it appears that, with the proposed arrangement of auxiliary steam pipes, superheated steam can be supplied to all auxiliaries & accordingly, copper pipes should not be used for auxiliary steam & all fittings subjected to superheated steam should be made of Cast Steel or other approved material as required by Sections 13 & 22 of the Rules for Engines & Boilers.

Return *9* plans *S*

Retain *9* copy *S*.

*Lr 5/1*

*WDA*  
*J.R. 62*  
*CM*  
*8/1/40*



© 2019

Lloyd's Register  
Foundation

W154-0204