

(LLOYDS REGISTER.)

G. R. 130
Lloyds.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any)

Official Number.	Name of Ship.	No., Date, and Port of Registry.
122705.	" Onward "	³⁸ 1905. Grimsby.

No., Date, and Port of Previous Registry (if any).

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Screw.	Selby	1905.	Bohrane & Co Selby

Number of Decks	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	115	0
Rigged	Ketch	Main breadth to outside of plank	21	6
Stern	Elliptic	Depth in hold from tonnage deck to ceiling at midships	11	57
Build	Clincher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards		
Galleries	-	Depth from top of beam amidships to top of keel		
Head	-	Depth from top of deck at side amidships to bottom of keel		5
Framework and description of vessel	Steel Drawler	Round of beam		3
Number of Bulkheads	Three	Length of engine room (if any)	30	
Number of water ballast tanks, and their capacity in tons	-			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel	tons.	Ditto per inch immersion at same depth	tons.
--	-------	--	-------

PARTICULARS OF ENGINES (if any).

No. of Engines.	Description.	Whether British or Foreign made.	When made.	Name and Address of Makers.	No. of and Diameter of Cylinders.	Length of Stroke.	N. H. P. I. H. P. Speed of Ship.
One Set.	Triple Engines, Expansion direct acting Inverted cylinder Boilers. Number..... One Iron or Steel..... Steel Pressure when loaded 180lbs.	British	1905	Charles D. Holmes & Co Hull	Three 12" 21" 34"	24"	60 420 10 1/2 Knots

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	194. 15	On account of space required for propelling power	103. 60
Closed-in spaces above the Tonnage Deck, if any		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Space or spaces between Decks		These spaces are the following, viz.:-	
Poop	11. 80	Forecastle cabins	26. 89
Forecastle	2. 13		
House	. 54		
Other closed-in spaces, if any, as follows:-			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894, if required.		Deductions under Section 79 of the Merchant Shipping Act, 1894, as follows:-	
		Cubic Metres	
Gross Tonnage	208. 62	Master 1.89	5.39
Deductions, as per Contra	135. 88	Boon's stores 3.50	
Registered Tonnage	72. 74	Total Deductions	135.88

Name of Master John Haynes Certificate of Service No. Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.
Forward Steam Fishing Company Limited, of Great Grimsby } shares. 64
County of Lincoln.

Alfred Bannister of Fish Docks, Grimsby, Manager.

Dated 20 Oct. 1905.

