

MEMORANDUM.

Triple Screw Steamer "CERAMIC", No. 22498 in Register Book.

Owners:- Messrs. Shaw, Savill & Albion Co.Ltd.

Rule Dimensions:- 655' x 69' x 48' to upper deck
56.5' to bridge deck.

Scantling Nos:- 31400 and 76600

Proportions:- Length = 13.65 depths to upper deck
11.6 depths to bridge deck.

Summer moulded draught = 34'-6".


This vessel was built by Messrs. Harland & Wolff, Ltd. in 1913, and was not classed with any Classification Society.

Capt. Noal, the Owners' Representative, stated that he contemplated classing the vessel with this Society, but before submitting the proposal officially he desired that the scantlings and arrangements be examined with a view to seeing whether they were such as could be recommended to the Committee for the class 100A with a freeboard corresponding to the above draught. His representative therefore handed in a plan of midship section, together with an outline general arrangement plan.

The scantlings and arrangements have been examined, and it is found that certain items of the double bottom are not equal to the tabular requirements, as four side girders are fitted, port and starboard, instead of two as required by the Rules, & it is considered that the bottom structure as fitted is equivalent to the rule requirements.

The framing, beams and topsides and deck are all either equivalent to or in excess of the tabular requirements.

Capt. Noal has therefore been informed that so far as the scantlings and arrangements shewn on the plan of midship section are concerned they are such as would entitle the vessel to be recommended to the Committee for the class 100A- with a freeboard corresponding to a summer moulded draught of 34'-6".

 Lloyd's Register
Foundation
6. 1. 36.