

One Compound two Crank

W1581-0061

Telegrams: "LOWATT, GLASGOW."
A B Code Used.

Post Office Telephone No 231.
Goods Address: 154 West George Lane.

Contractors to the Canadian, Indian, Egyptian, Japanese, Russian, Sydney, and Western Australian Governments; Suez Canal Co.; Great Central, Great Eastern, L. & Y., L. & N. W., London and South Western, Midland, North Eastern, and North British Railway Cos.; Clyde Frusters, East London Harbour Board, Natal Harbour Board, Mersey Dock Board, and many of the principal Shipbuilders, Engineers, Iron and Steel Works, and Manufacturers, &c., in the United Kingdom.

J. CHARTERS,
Electric Light and Power Engineer.

261 West George Street.

Glasgow

Sole Agent for "Phoenix" Generators and Motors.

Send Grams No. 455.

Circuit	Lamps in Circuit	Current amps	Conductance	Area of bond? sq"
Aft Cluster	3 - 300 CP.	18	$\frac{7}{16}$.02227
Forward Cluster	3 - 300 CP.	18	$\frac{7}{16}$.02227
Pump Engine Rm.	10 - 16	5.6	$\frac{7}{32}$.00705
Propeller Engine Rm.	18 - 16	10.0	$\frac{7}{16}$.01254
Officers Quarters	16 - 16	9.0	$\frac{7}{16}$.01254
Crew Port	9 - 16	5.0	$\frac{7}{32}$.00705
6 Deck Lts. Forward	6 - 50	3.3	$\frac{7}{32}$.00705
Forward Winch	3 - 50	5.0	$\frac{7}{32}$.00705
Accommodation Aft	8 - 16	4.5	$\frac{7}{32}$.00705
Storehold	7 - 16	4.0	$\frac{7}{32}$.00705
Navigation Captain	3 - 16 CP. + 3 - 32 CP.	5.0	$\frac{7}{32}$.00705
Crew Starb'd.	9 - 16 CP.	5.0	$\frac{7}{32}$.00705
4 Deck Lts Aft	4 - 50 CP.	7.0	$\frac{7}{32}$.00705
Stern Winches	4 - 50	7.0	$\frac{7}{32}$.00705
Single lamps	- - - - -	.56	$\frac{1}{16}$.00181