

— TWIN SCREW PUMP HOPPER DREDGER —
 — TO CLASS A1 AT LLOYDS SPECIAL SURVEY + —
 — SCALE $\frac{1}{2}$ = 1 Foot —

DIMENSIONS

LENGTH ON DECK	-----	
LENGTH BETWEEN PERPS	-----	280' - 0"
BREADTH MOULDED	-----	45' - 0"
DEPTH	-----	18' - 9"

NUMERALS

HALF BREADTH	22.50
HALF GIRTH	34.87
DEPTH	19.68
	<u>82.05</u> = 1 ST NUMBER

$$\frac{16410}{22836.9765} = \text{PLATING } N^{\circ}$$
 Теллеров
 Эксперимент $\frac{488}{23324}$

RIVETING.

FORE & AFT LANDINGS OF SHELL TO BE DOUBLE RIVETED
F. -- " -- HOPPER & WELL TO BE SINGLE
BUTTS OF WELL TO BE STRAPPED & TREBLE RIVETED ~~WELL~~
~~TO BE STRAPPED AT ENDS~~ BUTTS OF HOPPER PLATING
TO BE LAPPED & DOUBLE RIVETED. BUTTS OF WELL TO
BE STRAPPED & -- --
DECK LANDINGS SINGLE RIVETED. BUTTS LAPPED & DOUBLE
RIVETED FOR 1/2 L. SINGLE AT ENDS.
REMAINDER OF SHELL LAPPED & TREBLE RIVETED

EQUIPMENT

✓ 2, 45 CWT TROTMAN'S STOCKLESS ANCHORS
✓ 2, 35 " " " "
✓ 1, 6 " KEDGE ANCHOR

- CHAINS -

✓ 240 FATH ⁿ 17/8 STUD LINK CHAIN
✓ 80 " 1 1/16 SHORT " "
✓ 60 " 7/8 " " "

— HAWSEYS —
120 FATHOMS 4" FLEXIBLE STEEL W
120 " 3" " "
120 " 3½ " "
2 COILS 90 FATH 4" MANILLA

SECTION THROUGH WELL.

SECTION AFT OF HOPPER-

SECTION THROUGH HOPPER

Thos W. Simons Esq

No 485

Quadrup Section re.


For
Government of Southern Nigeria

1850 Ans

"Sand Grouse"

GLASGOW Report No. 27918

GLASGOW REPORT No. 29429.



RETAIN



© 2021

Lloyd's Register
Foundation

W 581-0063