

of Quebec.

July 6th. 1919.

R. Lee Annear,

the Imperial Munitions Board, Montreal, survey the wood
S. S. "WAR WINGAN" 2216 tons gross register, for the
purpose of ascertaining the nature and extent of the
damage alleged to have been sustained through encountering
ice, while on a voyage from Three Rivers P.Q. to Quebec,
on the 4th, to 6th, December 1918.

On the 20th, May 1919, and subsequently the
vessel being in the Levis Dry Dock.

Upon examination found, the planking on both
sides of the vessel in way of the light line scrubbed
and cut, the oskum hanging from the butts and seams and
the copper earth in the ships side torn.

It was recommended that there should be renewed
eight planks on the port side, and seven planks on the
starboard side, that the adjoining planks be dressed, and
that there be fitted seventeen graving pieces on the
port side, and seven graving pieces on the starboard
side, that the vessel be caulked from the keel upwards,
and that the copper earth be repaired, that the fastenings be



© 2021

Lloyd's Register
Foundation

W1592-0021 1/2

overhauled and the bottom recoated with two coats of copper paint.

The jacking repairs were effected at this port.

Fee \$50.00



© 2021

Lloyd's Register
Foundation

W1592-0021 1/2