

W162-0023

Thomas B. Thrige

Odense

R / EA .

T.A.

TEST-SHEET.

Order No. ^A 11000 19 39 , from Ingeniørforretningen TRIUM, (TBT.Købhvn.K.)

Machine No. 812200

tested as shuntmotor

Date 31/5- 1939 .

Type	K 8	10 ^{H.P.} XXXX	220 Volts	38	Amps.	2300	Rev.
------	-----	---------------------------------------	-----------	----	-------	------	------

Armature No: 4 x 73529 4 Brushes No: KZU , Dimensions 12,5x20, Quality K 135 .

Hour	Terminal Volts	Line Amps.	Shunt		Rev.	Air- temp. °C	Remarks
			Volts	Amps.			
11.30	223	38	223	0,58	2280		
	221	"	221	0,55	2340		
14.00	221	38	221	0,55	2340		
	220	38	220	0,54	2320	25,5	
	225	4,3	225	0,54	"		

Temperature rise:

Armature: 18 °C, Shunt: 17 °C.

Series-winding: - °C, Interpoles: 17 °C, Commutator: 24,5 °C

	220	47			2320	for 30 min.
	219	56			2330	" 1 "
	216	76			2320	" 15 sec.
The temperature-rises are measured at machine no. 811893, which is exactly similar to this .							

Copied Rep. No. 1111

Insulation: Test voltage: 2000 volts for 1 min. — Resistance: 100 megohms.

Manufactured and tested in accordance with British Lloyds rules .

M/S DANMARK

Odense, Denmark

16/2 - 1940

pr. THOMAS B. THRIGE

BILGE PUMP.

Handwritten signature